

of Om  
 Viewers  
 of St. Mil-  
 ann and  
 of the Viewers  
 rich un-  
 y Road No. 389,  
 East, in  
 Survey 389,  
 dist.  
 d from  
 angles  
 on E. side  
 mounted  
 37 E.  
 sub. sec. line,  
 S. = O. R 346  
 sub. sec. line,  
 culvert,  
 W. & S. E.  
 8.  
 over Sec. 18.  
 side of lane.  
 s. 18 + 19.  
 house  
 orchard  
 dist.  
 to Secs. 17-18-19-20.  
 Secs. 19 + 20

Course	Distance	Sum	Notes
	77.00		Cor. to Secs. 19-20-29-30, Int Road Survey 346
	80.0		Set 3 mile post 45 links E. of line.
S 75° 55' E	7.10	L. 75° 55'	Set angle post MKD. 10.
	21.07		Ravine water runy. course S. - 5' culvert needed.
S. 6° 15' W	26.96	R. 92° 10'	Set a. p. MKD. 11. Descend.
	27.90		Brook 4 lks. wide runs west.
	29.75		" 6 " " " "
S. 42° 55' E	33.10	L. 49° 10'	Set a. p. MKD. 12
S. 52° 25' E	43.90	L. 9° 30'	" " " 13, by fir stump 24 ins. dia.
S. 40° 32' E	57.70	R. 11° 55'	" " " 14
S. 78° 32' E	59.86	L. 38° 00'	" " " 15
S. 51° 47' E	64.08	R. 11° 45'	" " " 16 " " "
S. 68° 02' E	67.11	L. 16° 15'	" " " 17
S. 63° 52' E	71.27	R. 4° 10'	" " " 18
	80.00		A tamarack 4 ins. dia. bears S. 11 lks. dist. MKD. 4 m, for 4 mile post.
S. 37° 07' E	0.94	R. 26° 45'	Set a. p. MKD. 19
S. 53° 52' E	7.16	R. 16° 45'	" " " 20.
S. 39° 42' E	13.48	R. 14° 10'	" " " 21.
N. 83° 18' E	19.69	L. 57° 00'	" " " 22, 10 lks. S. of line.
" 68° 30' E	24.64	L. 14° 40'	" " " 23, Cut on stump, on line.
S. 87° 14' E	29.80	R. 24° 05'	" " " 24
S. 78° 44' E	35.68	R. 11° 30'	" " " 25
S. 62° 34' E	41.12	R. 13° 10'	" " " 26 15 lks. W. of line.
S. 21° 43' E	49.95	R. 40° 51'	" " " 27
S. 42° 53' E	54.10	L. 21° 10'	" " " 28
S. 66° 63' E	70.90	L. 24° 10'	" " " 29
S. 47° 41' E		R. 19° 22'	" " " 30
	80.00		Set 5 mile post 30 lks. North of line.
S. 32° 26' E	22.5	R. 15° 15'	" " " 31
S. 71° 36' E	72.5	L. 39° 10'	" " " 32, also cut 32 on S. side of stump 20 lks. North.
S. 54° 46' E	23.80	R. 16° 50'	" " on line " " 33 on fir tree 10 ins dia 22 " "
S. 34° 53' E	39.42	R. 19° 53'	" " " " " " 34 " stump 5 lks. north of line,
S. 21° 53' E	53.00	R. 13° 00'	" " " " " " 35 " fir 11 lks. East of line
S. 73° 13' E	69.75	L. 51° 20'	" " " " " " 36 " tamarack 26 dia. 1/2 lks. South.
	80.00		A fir tree 6 ins. dia. bears north 35 lks. dist.
S. 84° 13' E		L. 11° 00'	Marked VIM and 37 for 6 mile post.
			Drive a. p. on line.
S. 45° 23' E	9.90	R. 35° 50'	Set a. p. on line and 38 on fir 14" dia. 16 lks. N. of line
S. 63° 53' E	15.77	L. 18° 30'	" " " " 39 " " 36 " 31 " " "
N. 87° 52' E	23.95	L. 26° 15'	Set a. p. on line and cut 40 on fir 24" dia. 11 lks. S.W. of line
N. 72° 02' E	40.87	L. 15° 50'	" " MKD. 41