

Course	Dist	Sum	
S. 67° 05' E.	43.27	R. 40° 50'	" " on line " " 42 " fir 6" dia. 4 lks S. of line
S. 27° 51' E.	47.86	R. 39° 17'	" " mkd 43. Descend.
S. 41° 11' E.	52.60	S. 13° 20'	" " on line and cut 44 on fir 30" dia 4 lks. S. of line
	60.00		Foot of descent. - ascend
	65.00		Summit.
S. 9° 05' E.	71.50	R. 38° 06'	" " mkd 45
S. 12° 50' E.	74.40	S. 4° 45'	" " " " 46
S. 35° 45' E.	78.90	S. 25° 55'	" " on line and 47 on fir 16" dia. 6 lks. S. of line.
	80.38		a fir tree 30 ins. dia. bears S. 3 links distant,
	7.50		mkd 7 M. for 7 mile post
			ascend hill
N. 46° 00' E.	9.40	S. 98° 15'	Set a. p. on line and cut 48 on fir 18" dia. 12 lks. W. of line
S. 87° 00' E.	16.45	R. 47° 00'	" " " " " " 49 " Stump 9 lks. N. " "
S. 36° 55' E.	28.00	R. 48° 05'	" " " " " " 50 " " 24" dia. 9 lks. W. " "
S. 57° 10' E.	37.92	S. 20° 15'	Cut 51 on fir 60" dia. 2 lks S. of line (Snow 4' deep)
	40.00		Summit - Descend.
N. 70° 10' E.	46.92	S. 52° 40'	Set a. p. on line mkd. 52 (Council angle)
S. 82° 35' E.	58.56	R. 27° 15'	" " " " and cut 53 on fir 10" dia. 5 lks. S. of line.
N. 76° 00' E.	63.02	S. 20° 30'	" " " " mkd. 54
N. 59° 40' E.	75.03	S. 17° 15'	" " " " " " 55
	80.50		a. fir 8 ins. dia. bears E. of line 16 lks. distant.
			mkd. 8 M for 8 mile post
N. 77° 00' E.	11.59	R. 17° 20'	Set a. p. on line and cut 56 on fir 14" dia 11 lks. East.
N. 55° 30' E.	16.96	S. 21° 30'	" " " " " " 57 " " 24 " 4 " "
N. 28° 10' E.	31.61	S. 27° 20'	" " " " " " 58 " " 18 " 5 " West.
	36.50		Int. Sinkton mtn, road.
	36.83		a dead fir tree 6 ins. in dia. on line. mkd R 389 for Terminus of Road 389.

All the posts were of legal size, and marked and set in mounds, as required by law -

The survey follows, in general, a well defined traveled road throughout, running for the most part through thick timber.

I hereby certify that the foregoing are the correct field notes of Road Survey No. 389 for Umatilla County, Oregon.

Jno. C. Arnold, County Surveyor.  
 Filed July 13, 1892  
 W. M. Pierce  
 Clerk

366 372 4 M.