

Field notes of Road Survey No. 393, for Umatilla Co Oregon
 I met A. M. Elam, R. Wells and Henry Frazier, at Milton Cr.
 June 17th 1892, at 9 a.m. and qualify them, each, according to law
 to act as viewers on Road Survey No. 393 for Umatilla Co, Or. - we
 call Henry Frazier and J. C. Hill to chain and mark, who were
 each duly sworn as required by law. after which, under
 direction of the viewers, I proceed to Survey Road 393, find stone
 cor. set by P. Zahner in the year 1877, as per plat made
 by him, for center of S.W. 1/4 of Sec 30 T. 6 N. R. 36 E., 2nd set
 initial post, against fence on E. side of lane, and 38 1/2 lks. of
 said stone cor. from which I run on traveled road in lane,
 course N. + S. - Descend gently.

north

18.87 Brook, in flat, 12 lks, wide, runs N. E.

20.08 Stone cor. set by P. Zahner, on line, in lane N. + S.

24.00 Ascend hill.

28.00 Summit

40.21 Stone cor. set by P. Zahner, on line, in lane N. + S.

50.30 Intersect rail fence on W. side of lane which makes
 a turn to the right from stone cor. at center of N.W. 1/4
 of Sec. 30. as described

60.21 Set temp to Sec. cor. - I make diligent search for this
 cor. as set by Mr. P. Zahner; failing to find the same
 I call Wm Kossberg, who assisted Mr. Zahner, and
 by whom the survey was ordered; procuring Mr. Zah-
 ner's field notes and plat, I reset this cor. 20 links
 W. of center of rail fence on W. side of lane. set
 angle post marked T, at cor. and turn R. 1°

N. E.

72.00 Descend.

73.50 Foot of descent.

80.00 Set 1 m. p. against fence on W. side of lane, and
 45 links E. of line

10.65 Cross fence on W. side of lane - Enter lane N + S

20.35 1/6 Sec. Cor. set by P. Zahner.

40.33 " " " " " " , center S.W. 1/4 Sec. 19.

Set R 393 on S. side of cedar fence post in fence
 on E side of lane 46 links E. of last described stone
 cor., for terminal post to R. 393.

I hereby certify that the foregoing are the correct field notes
 to Road Survey No. 393, for Umatilla County, Oregon

Jno. C. Arnold, Surveyor,

Filed July 13, 1892

W. M. Pierce

Clerk