

Witness our respective hands at Pendleton, Oregon.  
 this day of June A. D. 1892

Eugene Rieth  
 Burr Johnson  
 Hiram Flickinger } Viewers. Road  
 Survey No. 397.

Filed July 6. 1892  
 W.M. Pierce }  
 Clerk

Field Notes Road No 397

Field notes of Road Survey No. 397. for Umatilla Co. Oregon

I met Eugene Rieth, Burr Johnson and Hiram Flickinger, Viewers on Road Survey No. 397 for Umatilla Co. Ogn., after qualifying them, according to law. we call J. C. Hill and J. M. Jarvis to chain and mark, who were each like wise duly qualified - under the direction of said Viewers I proceed to the survey of Road No. 397: =

I cut R 397-0- on E. face of post at E end of Railing on the north or lower side of what is known as the upper McKay bridge and from the center of the east end of said bridge about 20 chs. S.E. of center of Sec. 34 T27N. R32E

Course	Dist. chs.	Turn	Remarks
N 14° 37 W	0.75	L. 62° 37'	Set angle post mkd. 1
N 46° 34 W	55.70	L. 31° 51'	" " " 2
	80.00		" 1 M. p 45 links E. of line.
N 31° 09 W	14.12	R. 15° 25'	Set a. p. mkd 3
N 23° 24 W	20.00	R. 7° 45'	" " " 4
N 41° 54 W	28.35	L. 18° 30'	" " " 5, Descend steep grade to creek bottom.
N 44° 31 W	29.23	L. 2° 37'	" " " 6
N 34° 53 W	58.40	R. 9° 38'	" " " 7
N 24° 53 W	66.87	R. 10° 00'	" " " 8
	70.83		Center line
N 19° 08 W	75.23	R. 5° 45'	" " " 9
	80.00		a basalt boulder 32 x 24 x 24 ins. brass west 45 lbs distant. marked 11 M for 2. m. point.
N 75° 25 W	14.17	L. 6° 20'	Set a. p. mkd 10
N. 72° 55 W.	19.15	R. 2° 21'	" " " 11
N 7-70 E	23.70	R. 30° 15'	" " " 12
N 70° 03 W	28.81	L. 27° 23'	" " " 13
N 40° 15 W	38.83	L. 20° 12'	" " " 14 J. Chrissinger's house, about 4 chs. N.W.
N 7-30 W	50.83	R. 32° 45'	" " " 15