

Field notes of Road Survey No 401 for Umatilla County Oregon
 I met H. S. Frazier Bro Dehaven and A. M. Eelan Viewers on Road
 Survey No 401 for Umatilla County Oregon, at Milton August 29th
 1892 and duly administer oath to each as required by law, H. M.
 Rinier and J. C. Hill called to chain and mark each of whom duly
 Qualified. Under direction of said Viewers I find a point 20.17 chs.
 South of $\frac{1}{4}$ Sec. Cor. bet. Secs. 26 & 35 T. 6 NR 35 E. W. M. supposing to be the
 $\frac{1}{16}$ Sec Cor. on the W body of the N $\frac{1}{4}$ of said Sec 35 This point is in
 the center of a traveled road in lane 62 links wide course N+S called
 the lower or west Walla Walla + Milton Wagon road; fences run E+W
 from points on opposite sides of the said lane, and a road notice
 has been posted on the E. side of said lane, at this point.

I set regulation initial post, against fence on E. side
 of lane 43 lks. N.E. of initial point as described, and run thence
 along fence Va. N. 21' E.

East

13.70 Creek 15 lks. wide, runs N. W.

19.45 Fence Course N. + S.

22.60 Creek 20 lks. wide Course N. W.

39.04 Stone Cor, supposing to be $\frac{1}{16}$ Sec. Cor.

55.50 Road bears N. + S.

58.47 Hub in center of plowed furrows, Course E+W $\frac{1}{4}$ 30 lks
 dist both N. + S. from said hub which has a tack in
 top and from which, on opposite sides of the
 said furrows there is a plowed furrow, Course N. + S.

58.87 a point in center of space included between said
 parallel furrows running E. + W. 60 lks dist from
 each other and similar parallel furrows running N. + S.
 40 lks. dist. from each other. at this point there is
 a post in stone mound, on which post a road notice
 has been posted. I set terminus 45 links S. W. of said
 center point in angle made by said furrows,
 all the posts are of the size, and are marked and
 set in mounds, as required by law.

I hereby certify that the foregoing are the original ^{and}
 correct notes of road survey no 401 for Umatilla County,
 Oregon.

Jno. C. Arnold. Surveyor

Filed Sept 5-1892

W. M. Pierce

Clerk

Sh plat

Filed