

Field Notes of Road Survey No. 409, for Umatilla Co Oregon
 I must J. M. Humphill, Geo Oloth and Fred Ginger at Milo
 Palmers residence. Dec. 10 1892. and qualify each as viewers
 on Road No 409 for Umatilla County Or. We call A. M. Pitman and
 J. C. Hill to chain and mark, who qualify as per, law. Under
 direction of said Viewers, I set initial post 30 feet E of N. E. cor.
 Sec 13 T. 1 N. R. 32 E. and from said Cor. Stone.

| | | |
|--------------|------|--|
| | feet | Down on line bet Secs. 12+13 |
| West | 150 | Descend. |
| | 700 | Ravine. Course N. 30° W, ascend. |
| | 400 | Top of hill, level |
| | 1300 | Descend gently. |
| | 1700 | " Steeper |
| | 7000 | " Steepest |
| | 7150 | Foot of hill |
| | 7455 | Ravine 10 ft. W. Course N. W. |
| | 7648 | The 14 Sec Cor Stone bet Secs. 12+13 |
| | 3030 | Descend steep pitch |
| | 3130 | Foot of Descent |
| | 5272 | Set 1 M. P. 70 ft. N. of line at Cor fence, N+E. |
| | 16 | The Cor. to Secs 11-12-13-14, angle 4 on R. 382. |
| N 35° 00' W | 737 | set angle post mks. ↑ on E = Int. R 382 = Turn R 55° Irrigating ditch 2 ft deep + 4 ft wide Course west. |
| | 880 | Ravine 10 ft. Wide, Course W. |
| | 1430 | Set A. P. 2 at mouth of ravine. coming from N. and turn thence, S 68° |
| S. 77° 00' W | 1900 | Set A. P. 3 in alkali flat and turn thence S 51° 30' |
| S 75° 30' W | 7010 | Ravine 10 ft. Wide Course W |
| West | 3035 | Set A. P. 4, point 30 ft N. of line bet. Secs 11+14, thence on line parallel to Sec line, 30 ft N of same |
| | 3050 | Same Course N+S. |
| | 3658 | E. Bank of McKay Creek, Course N. |
| | 3740 | W " " " " |
| | 3910 | Int. N+S. line 30 ft. N. of 14 Sec. Cor. bet. Secs. 11+14 set A. P. 5 W bank of Irrigating ditch 8 ft. wide Course N. turn thence. |
| South | 3970 | Set A. P. 6, thence on line parallel to sec line, 20 ft. N. of same |
| | 4170 | " " 7, 30 ft. E. of rock cliff, about 15 feet high turn thence, to avoid said cliff S 65° |
| S 75° 00' W | 4237 | Set A. P. 8, 8 ft. West of fence Course about N 30° E + S 30° W |
| N. 70° 00' W | 4410 | Int. line bet. Secs. 11+14 set A. P. 9. Turn thence on sec line |
| West | 5280 | Set 2 M. P. 30 ft. S. of line |
| | 554 | Cor. to Secs. 10-11-14-15- Int. R. No. 370 |

185
 232
 miles
 set in
 409 for
 filed
 W
 then
 road
 and

Filed