

Field notes of Road Survey No. 412 for Umatilla Co. Oregon

Athens Umatilla Co. Oregon, Dec 13. 1892

I met Wm Willoughby, D. C. Stanton and Frank Mansfield Viewers on Road Survey No 412, and Qualify each as per law. We call H. M. Ritter and D. C. Stanton to chain who each Qualify after which under direction of said Viewers I find initial post, set by me July. 15 1892, in Road Survey No 385 which post is set on N. Side of E & W. lane and 40 links N. of 116 Sec. Cor on E 1/2 of line running E & W through center of Sec. 19 T. 4 N. R. 35 E. I repair Md. around the post, leaving it 4 ft base x 7 ft high and cut R 412 on S. face. From said 116 Sec. Cor. I run along center of narrow lane, course N + S, through center of Sec 14 Sec 19.

- South ^{Set} 1950 A house (Ely) brass E about 80 ft. dist.
- 2430 N. end of bridge across Wild horse Creek course West.
- 3524 Set A.P. Mk. 1 on N. driven even with surface, in sandy bottom, 70 ft. N. of Cor. of fence S. + S. E. thence I run
- S52° 21' E 4345 Along traveled road up creek, to bridge 70 long across W. H. Creek, course about North.
- 4427 A.P. Mk. 2, driven even with surface, in R. thence
- S. 40° 51' E 4734 N. end of bridge across W. H. CK. course N. E. } ascend
- 4814 S " " " " " " }
- 4987 a.p. Mk. 3, about 6 ft E of trav R House brass } about 175 dist, thence I run,
- S. 15° 21' E 5280 Set 1 M.P. 70 ft. S. or E. of line. Continue course ascend,
- 154 A.P. Mk. 4, Int. line bet Sects 29 + 30, thence along said line
- South 477 This 1/4 Sec. Cor. bet. Secs. 29 + 30
- 1000 Summit
- 1803 A.P. Mk. 5, Cor fencing N + E, thence along fence,
- East 2056 " " 6, thence along road in lane
- South 3382 " " 7, Int. line bet. Secs 29 + 32, thence along said line
- West 3640 This Cor to Secs 29-30-31-32, finding the post at this cor

in danger from decay, I set a triangular pyramidal shaped semiginous basalt stone, marked 5 notches on E end and 1 notch on S. Size of stone 7x7x7 ins. by 11 ins. long set 20 ins. in ground 30 ft. S. W. of this post I set terminal post in Road Survey No 412. All the posts are regulation, as per law, in size, marks, mounds + C.

I hereby certify that the foregoing are the correct field notes of Road Survey No 412 for Umatilla County Oregon

Jno. C. Arnold
Co Surveyor

Filed Jan 3. 1893
W. H. Pierce
Clerk