

- 2539 " " " $\hat{38}$ " " Right $13^{\circ} 16'$ Prob Sec. cor. Left $78^{\circ} 16'$ about 500'
- 3472 " " " $\hat{39}$ " " Right $38^{\circ} 44'$ S of Trar. R. 6 ft dist.
- 5000 Summit of hill brs. E + W - stony - Descend to Big Pot
- 5312 A pyramidal shaped stone in place 24 ins base and 15 ins. high MKd 11M on N. face in mid. of stone, 4 ft. base $\times 2$ ft. high, 30 ft. South of line.
- 97 Set a P. MKd. $\hat{40}$ and turn left $8^{\circ} 40'$
- 160' Sub. line of Stone Mounds, bearing E. + W.
- Sept 23^d. 1892
- 1122 Set a P. MKd $\hat{41}$ and turn left $11^{\circ} 13'$ \odot left of line 3 ft.
- 1907 " " " $\hat{42}$ " " Left $22^{\circ} 17'$
- 2648 " " " $\hat{43}$ " " Right $9^{\circ} 48'$
- 3068 " " " $\hat{44}$ " " Left $3^{\circ} 17'$
- 4000' Crnk about 6 ft. wide course N. W.
- 4549 Set a P. MKd $\hat{45}$ and turn Right $18^{\circ} 57'$
- 5133 Fence brs E + W. Gateway for road
- 5384 A pine tree 24 ins. dia MKd. 13M on E. brs left 50' dist.
- 30' Cross Crnk about 6 ft. wide, course N. W
- 1069' Set a P. MKd. $\hat{46}$ and turn Right $19^{\circ} 45'$
- 3084 " " " $\hat{47}$ " " Right $17^{\circ} 09'$
- 4282 " " " $\hat{48}$ " " Left $48^{\circ} 30'$
- 4656 Fence N. + S.
- 4900 Road to Penleton brs N. W. + S. E.
- 5280 Set a basalt stone 24 x 12 x 6 ins. MKd. 14M, in stone mid. 3 ft. base x 18 ins. high on hill side sloping S. W.
- 716 The N. W. Cor. of Sec. 32 T. 4 S. R. 30 E.
Set terminus at this cor. = saved fir 4 ins sq. and 4 ft. long MKd. R 406 on S.
all the posts, stones, + c used in marking out the road are of proper size and are marked and set in mounds according to law for the same.
- Sept 24th 1892.

I hereby certify that the foregoing notes for Road Survey No 406 for Umatilla County Oregon are correct.

Jno. C. Arnold
County Surveyor

Field Notes Filed Nov 9, 1892
W. M. Pierce
Clerk