

Field Notes of Road Survey No 426
for Umatilla Co. Or.

I meet G.W. Rigby, Geo Shurtum and Frank Brown viewers on Road Survey No 426 at Court House Friday June 9th 1893. and administer usual oath to each. I call Edgar Thoruson and Olney L. Burnham to chain and mark. Each of whom qualified according to Law.

I find point on each line of the Reserve Add to Peudleton in centre of mouth of lane, Run'g Eastward from E. end of Court Street 26.5 ft. Southward from Mon No 14 and 70 ft Southward from Centre of R. R. Track said point I take as commencing of Road Survey No 426, and set the Initial post .38 ft. S. of Pt. of Commencing and run thence

- S. 80° 00' E 1000 Set angle post mkd ↑ on each side of lane 46' W
I turn thence R. 7° 16'
- S 72° 44' E 1025 Descend about 8 ft
1200 Centre of Draw. course about North Ascend 8 ft
1408 Summit.
1425 Set ang. post mkd ↖ on each side of lane 56.5 wide
I turn thence S 5° 00'
- S 77° 44' E 1900 Set angle post mkd ↗ on each side of lane 60.8 wide
I turn thence S 14° 23'
- N. 87° 53' E 1925 Descend
2170 Centre of R.R. track
2202 Int N.S. line, through Centre Sec 122 N.W. 32 E.
2338 Set Ang. post. mkd ↖ on each side at R.A. N.S.
L. 10' by fence on N of R and Right 15' on bank
I turn, thence. R 17° 10' Descend from bench
- S. 74° 57' E 2665 Set ang. post. mkd ↗, against fence on N. side of R.R. Track. 70 dist from centre of same. from this point I turn R. 5° 35', and run on line 70 Northward. from centre of R. R. track and parallel thereto, said line to mark N. line of a 40' road.
- 3350 Pat Kines house bears N. about 400 ft dist
5240 Int W. line of S. J. R 70. N of centre of R.R. 2.
Set post. mkd. R426. on W. face. at pt of intersection
All the posts used are of Legal Size and are correctly marked and set in mounds.

I hereby Certify that the foregoing are the correct field notes for R. Survey No 426 for Umatilla Co. Or.
Jno. C. Arnold, Co Surveyor.

Filed July 20th 1893.
Umatilla
Clark