

Field Notes of Road Survey No 437. for Umatilla  
County, Oregon.

Monday, Oct 23<sup>rd</sup> 1893. I meet G. A. Barrett and  
Geo. B. Stamper, at 9 A.M. and administer  
Oath of qualification for viewers on Road  
Survey No 437 for Umatilla Co Or, as directed  
by law. Malon Hastings and S. D. Morgan were  
called to chain, and mark, and duly qualified.  
I set initial post, in Road Survey No 437. 28 link North  
of the 14 Sec cor. bet secs 3 & 4, in T 37 N R 36 E, and from said  
14 Sec. cor. I run on line bet said Secs 3 & 4

South	17.00	Ravine course W. well bears W about 60 lks dist,
	15.00	Old Road E & W = Smiths house bears E, about 150 lks,
East	20.00	Set post. mtd 1 and turn on level summit, enter timber,
	35.00	Ravine course N. ascends gently
	40.00	Fence. N & S.
	59.00	" "
	80.00	Set 1 MP. on line. on Summit. continue course
	87.6	Leave brush and timber. Set post mtd 2, thence
N 69°-25' E	17.30	Set post mtd 3 by E & W fence, about 100 lks S of Mr Muirheads, thence, I run
S 67°-55' E	35.00	Set post. mtd 4 70 lks N of E & W. fence on N. side of lane and about 100 links N.W. of Cor fence N & W. thence. I run
N 59°-05' E	35.70	Fence N & S.
	38.50	Ravine. course S.
	42.50	Ascend gently, through brush and timber.
	52.00	Summit. Enter dense brush
	53.50	Descend gently.
	55.00	Head of Ravine
	56.00	Old Road. nearly N & S
	72.50	Set post mtd 5 thence I run
N 17°-50' E	73.00	Old Road bears N E & W
	77.50	" " N & S
	80.00	Intersect Road Survey Nos 337 & 405, at a point 63 lks West of the 9 MP. on Survey 405. I cut R 437 on SW of white fir, 14 in dia, 28 lks E of Pt of intersection

All the posts are of regulation dimensions and are legally marked and set in mounds.

I hereby certify that the foregoing are the correct field notes of Road Survey No 437, for Umatilla Co Oregon.

Filed Nov 7<sup>th</sup> 1893  
Wm Pierce Clk

Geo. B. Arnold  
Co Surveyor.