

Field Notes of Road Survey No 431 for Umatilla County, Oregon +

I meet H.L. Frazier and Geo. DeStaven Viewers on Road Survey No 431 for Umatilla Co Oregon, at Riv. of D.L. French, on Linkton Mountain, Oct 26th 1893 and administered to each the usual Oath of qualification +

We call S.D. Morgan Jas. G. Thomson to chain and D.L. French H.L. Frazier & Omar Olinger to assist as may be required, I administered Oath of qualification to each of the chainmen, after which, under direction of said viewers, I cut R. 431 on SW of tree terminus of Road Survey No 389, at intersection of said Survey 389.

commonly known as the Weston Road, with the Linkton Mtn Road, and from a point S 69° 50' E of said tree, assuming a var of 21' E, I run ^{2 lines} but ↑ on N of white fir 10 ins dia. 9 lks S of line

nd
1
No 84,
tain Road
here the
Weston
regon
appointed
llowing
onorable
eyor
nd were
and
pointments
nson.
yor, each
ted said
We
ch
The one
s No
431.

S 36° 50' W	8.34	Set stake m ^{ks} 5 ↑ on line, on N hill side
N 81° 46' W	11.95	" " " 6 " " L, of trav, road
N 47° 50' W	16.37	" " " 7 " " R " " "
N 15° 40' W	19.66	" " " 8 " " R " " "
N 30° 15' W	22.85	" " " 9 " " R " " "
N 49° 55' W	27.50	" " " 10 " " " " " Foot of hill
	30.49	" " " 11 " " " " " "
N 36° 55' W	36.51	" " " 12 Bergardens fence bears L about 50 lks
N 28° 17' W	43.13	" " " 13 R of trav. R
N 58° 37' W	54.30	" " " 14 " " " " " "
N 78° 47' W	60.41	" " " 15 " " " " " "
S 60° 43' W	70.39	cut ↑ on S of white fir 21 lks S of line, also, stake m ^{ks} 11 on line
S 83° 30' W	78.30	Set stake m ^{ks} 12 ↑, about 200 lks N, of Smiths brush fence
N 34° 30' W	80.00	cut 1.M on south of dead fir 24 ins, dia. 28 lks E of line
	6.88	Set stake m ^{ks} 13 L, of trav road
N 30° 00' W	14.49	" " " 14 " " " " " "
N 45° 15' W	21.09	" " " 15 R " " " by cord wood.
N 41° 10' W	34.50	" " " 16 L " " " "
N 29° 35' W	45.34	" " " 17, and cut ↑ on NW. fir 12 ins, dia. 10 lks S 55° E of line
N 52° 50' W	63.71	" " " 18 " " ↑ on fir 4 ins, dia 23 lks S 19° E of line
N 22° 10' W	69.75	Int. line bet. Sec's 22, 23 & 24 NR 37 E. 237 lks, West of Cor. to Sec's. 22, 23, 26 & 27
		Set stake m ^{ks} 19.
N 46° 15' W	80.00	Set v. m. p. on line in stone mound.
	4.73	" stake m ^{ks} 20, 20 lks S. of E & W fence.
S 72° 25' W	9.75	" " " 21 on line.
S 44° 55' W	18.67	" " " 22 " " "