

Road
 ter marked
 berly from
 River in
 d running
 road up
 e between
 onship
 road to be

marked in the manner provided by law, as will more fully appear by the certified return of said Surveyor of said Road, which is herunto attached and made a part of this report.

That in our opinion the said proposed road should be established for the following reasons:

1st. The road is much needed for an outlet to residents along the north fork of the Walla Walla river.

2^d. A good road is built and maintained within limits of the survey.

Dated this 25th day of June, 1894.

George DeStaven
 A. M. Claw
 H. L. Frazier

Viewers.

Oregon

Filed June 20, 1894

W. M. Fairce Clerk, C. M. Parice, Deputy

Field Notes of Road Survey No. 440, for Umatilla County, Oregon.

I met A. M. Claw, Geo. DeStaven and H. L. Frazier, viewers appointed on Road Survey No. 440, at Bartlett's Hotel, in Milton, Oregon, at 8 a. m. June 28^d, 1894, and each qualifies as directed by law, J. L. Frazier and W^m Talbert qualify as chainbearers, after which under direction of said viewers, I set a fir post 4 ins sq and 4 ft long, 18 ins in ground, for initial post in road No. 440, post properly mtd, and set in mid of stone 4 feet base and 18 ins high. S 32° 17' 15" E dist from a thorn slate 3 ins in dia. marked R on E.

ble West.
 the peti=
 Milton, Or.,
 id day, the
 meeting
 Pitner,
 ating an
 ur appoint=
 lbert as
 ud lay out
 r opinion
 into con=
 expense
 ch road
 Surveyor,
 conspicu=
 noted, and
 the sides
 three
 nd all trees
 on the side
 road and
 ve been

Turns	Feet	From said thorn slate Iron S 88° 30' E.	chence
L 18° 40'	500	Set slate mtd 1	"
	980	Dam Dams house brs. about 60 ft S	"
R. 29° 00'	1200	Set 2, 6 ft N. of line of road	"
L. 20° 25'	1607	" 3,	"
L. 4° 52'	3845	" 4, 6 ft S of road on rock point	"
R. 34° 15'	4060	" 5,	"
L. 15° 46'	4580	" 6,	"
R. 12° 35'	4941	" 7,	"
	5240	Cut 1M on S side of elder tree 3 dia. 35 N of line on hillside.	"
L. 12° 10'	144	Set 8, 10 ft N of road line.	"
R. 6° 15'	882	" 9, 20 " " "	"
R. 30° 42'	1947	" 10, 6 " " "	"
L. 14° 30'	2800	" 11, 12 " " " mtd on stone at foot of hill.	"
L. 7° 25'	2774	" 12, 6 " " " " " "	"
L. 3° 20'	2938	" 13, 20 " " " " " "	"
L. 8° 50'	3857	" 14, 8 " " " " " "	"
R. 41° 00'	4020	" 15, 20 " " " " " "	"