

Thence East on line bet Secs 24 + 25

2160 5020 west bank of River

2375 5185 East " " "

83 5268 angle no. 7.

Thence South

85 5353 " " 8.

" S 22° 28' W

151 5504 " " 9.

" S 6° W

152 5656 " " 10

" S 58° E

152 5808 " " 11

" S 19° 25' E

242 6050 " " 12

Thence East

1552 76.02 creek course north

398 80.00 set post 4 feet long

and 4 inches square 20 feet north of line and marked 5 M.

Built mound 18 inches high and 4 feet wide at Base and dug Pits E and W of Post 5 feet dist

Thence East 246 Spring branch course north

1577 the center of Road angle 13

Thence north 894 2471 " " 14

Thence East between Secs 19 and 30.

2045 45.16 ditch course north

5529 80.00 set post 4 feet long and 4 inches

square 20 feet north of line marked 6 M. Built mound 18 inches high and 4 feet wide at base and dug pits E and West of post 5 feet dist.

Thence East on Sec line.

360 The corner to Secs 19, 20 - 29 and 30

3985 O.R. & N.R.R. course N 5° E S 5° W angle 15.

Thence S 77° E 132 41.17 Set post 4 feet long and 4 inches square 20 feet to the left marked R.T. no. 456 at the intersection with County road course South and East. Built mound 18 inches high and 4 feet wide at Base and dug Pits E and W. 5 feet dist.

I hereby certify that the foregoing Field Notes are correct to the best of my belief.

John W. Kimbrell  
County Surveyor

rest of a

line marked  
and dug

and 4 inches  
mound 18  
its N + S of

and 25