

We called to our aid  
 Ward Davis :  
 C.F. Weiss : Chainmen.  
 C.E. Macomber : Marker.

Who were by the surveyor each duly sworn. We viewed, surveyed and located said road, No 536, specified in our Order, and respectfully recommend that this road as located and Surveyed be adopted.

J.W. Arnold :  
 John S. Vinson : Viewers, Road Survey No. 536.  
 J.H. Raymer :

Field notes of Road No 536,

In accordance with an order issued by the Honorable County Court, of Umatilla County, at their March term, I met J.W. Arnold, J.H. Raymer and J.S. Vinson, at Freewater on April 6th, as specified and after duly qualifying as required by law, we adjourned until April 7 when we proceeded to the Initial point of road 536. We called to our aid Ward Davis, and C.F. Weiss who duly qualified as chainmen and proceeded to locate and survey Road #536.

I, planted a post 4" square 3-1/2 feet long \_\_\_\_\_ feet to the east 18 inches in the ground for a witness and dug pits and raised mound as per instructions.

Standard time 10'30"  
 Local " 10'25"  
 Declination of Sun 6°46'30"  
 Latitude 45°57'  
 Altitude 49°  
 Va. of Needle 21°55'

Field Notes of Road 536, Beginning at the center of Section 36 Tp. 6. N. R. 34. E. W. M.

Course	Dist	L.	R.	Total Dist	
North	2739	90°			
West	2541				
West	159		90°	5280	1 Mile post
North	1320	89°21'			N.W. Cor Sec 36
N. 89°21'	1508		72°15'		
N. 17°06' W.	2293			5280	2 Miles
" "	97	9°45'			
N. 26°51' W	620		27°10'		
N. 0°19' E	1170				1/4 Cor on N. line Sec 22

1700 End of Road, planted post feet W. 4" Square marked R.T. 536.18" in ground with mound and pits as per inst.

I hereby certify that the foregoing is a true and correct copy of field notes of road 536 as surveyed by me.

C.E. Macomber  
 County Surveyor.

ROAD No  
 537

IN THE COUNTY COURT OF THE STATE OF OREGON, FOR UMATILLA COUNTY.

In the matter of the petition of :  
 Frank Frazier and James McKay for:  
 Laying out locating and establis-:  
 hing of a road from the residence:  
 of the petitioner James McKay, on :  
 the Northwest 1/4 of Section 14 :  
 Township 2 North, Range 32 E.W.M. :  
 over and across the East Half of :  
 the southwest 1/4 of section 11, :  
 in said Township and Range, to and :  
 intersecting with the South end :  
 of Thompson Street, in the City of :  
 Pendleton, upon the south line of :  
 the Reservation Addition to the :  
 said City of Pendleton. :

REPORT OF VIEWERS. 537.

STATE OF OREGON :  
 COUNTY OF UMATILLA. :SS

We, the undersigned, having been duly appointed by the County Court of Umatilla County, State of Oregon, at the regular March term of said Court for the year 1902, to view, locate and lay out and establish a County Road and to view and assess damages to the lands of W.J. Furnish and John Armstrong by reason of the laying out, locating and establishing of the County Road from the residence of James McKay, on the northwest Quarter of Section 14, Township 2, North of Range 32 East of the Willamette Meridian, said road commencing at the barn yard gate upon the north side of the barn yard just east of the dwelling house, said point being about 880 feet north from the south line of the Northwest Quarter of section 14 aforesaid, and 450 feet west from the East line of the said Northeast Quarter of said Section, in said Township and Range; said dwelling house being upon the lands of the petitioners, to-wit: on the said Northwest Quarter of said section 14, Township 2 North, Range 32 E.W.M. and running thence upon the line of the road as it now exists across the said premises in a Northerly direction to a point upon the South line of the Southwest Quarter of Section 11, Township 2 North, Range 32 E.W.M., 13 chains and 42 links West of the Southeast corner of the said southwest Quarter of the said section 11, township 2 North, Range 32 E.W.M.; Thence running in a Northerly direction to the East of the line fence as it now runs, in a Northerly direction over and across the East half of the Southwest quarter of said Section 11, in Township 2 North of Range 32 E.W.M., to a point about 250 feet south of the line of the Reservation Addition