

8/3

FILE COPY



2003-4450519 1 of 3

445 0519

IN THE BOARD OF COUNTY COMMISSIONERS OF UMATILLA COUNTY

STATE OF OREGON

RECEIVED

IN THE MATTER OF LEGALIZATION )
OF A PORTION OF BIRCH CREEK ROAD,)
COUNTY ROAD NO. 550 )

AUG 20 2003

ORDER NO. RD2003-24

UMATILLA COUNTY RECORDS

WHEREAS, the Umatilla County Board of Commissioners may, under authority of ORS 368.201 to 368.221, order a county road that has been used and traveled by the public for ten (10) years or more to be surveyed and recorded, and

WHEREAS, the Umatilla County Board of Commissioners ordered the survey of Birch Creek Road (County Road #550), the midpoint of which is located approximately 4 miles northeast of Milton-Freewater in Umatilla County, Oregon, and lies in Sections 22 and 27, Township 6 North, Range 36 E.W.M, and

WHEREAS, the Notice of Hearing was posted and all owners of abutting property affected by the legalization procedure were served copies of the Notice of Hearing, and

WHEREAS, the Umatilla County Board of Commissioners on August 20, 2003, held a public hearing and finding that it would be in the public interest to legalize the road:

THEREFORE IT IS NOW ORDERED that the road be legalized as follows:

A 60-foot wide strip of land for road and utility installation purposes located in Sections 22 and 27, Township 6 North, Range 36 East of the Willamette Meridian, the centerline of which is more particularly described as follows:

Beginning at a railroad spike marking the Southwest Corner of Section 22, Township 6 North, Range 36 E.W.M.; thence S89°59'57"E, 705.61 feet; thence 200.01 feet along a 21,325.31-foot radius curve left The long chord bears N89°43'12"E, 200.01 feet); thence N89°26'21"E, 335.43 feet; thence 231.69 feet along a 461.09-foot radius curve right (the long chord bears S76°09'56"E, 229.26 feet); thence S61°46'13"E, 917.29 feet; thence 99.69 feet along a 507.75-foot radius curve left (the long chord bears S67°23'41"E, 99.53 feet); thence S73°01'11"E, 47.51 feet; thence 49.84 feet along a 253.35-foot radius curve left (the long chord bears S78°38'41"E, 49.76 feet); thence S84°16'11"E, 45.88 feet; thence 49.95 feet along a 431.90-foot radius curve right (the long chord bears S80°58'31"E, 49.92 feet); thence S77°40'53"E, 154.29 feet; thence 99.98 feet along a 1687.70-foot radius curve right (the long chord bears S75°58'55"E, 99.96 feet); thence S74°16'59"E, 297.20 feet; thence 554.39 feet along a 6943.40-foot radius curve left (the long chord bears S76°34'11"E, 554.24 feet); thence 166.25 feet along a 652.85-foot radius curve right (the long chord bears S71°33'44"E, 165.80 feet); thence S64°16'14"E, 81.61 feet; thence 249.55 feet along a 249.55-foot radius curve left (the long chord bears S68°32'25"E, 249.32 feet); thence S72°48'37"E, 248.62 feet; thence 305.72 feet along a 750.06-foot radius curve left (the long chord bears S84°29'12"E, 303.60 feet); thence N83°50'12"E, 716.26 feet to a railroad spike set flush with the asphalt surface at the centerline of Hood Road which bears S01°31'26"E, 1104.24 feet from a railroad spike marking the Southeast Corner of Section 22, Township 6 North, Range 36 E.W.M.

Original to: Commissioner's Journal
Copy to: Doug Olsen, County Counsel

and the terminus of this description. EXCEPTING THEREFROM that portion of the above described road lying within the right-of-way of Hood Road.

The plat of the above described road is recorded as Survey No. 03-105-C in the Umatilla County Surveyor's Office.

Dated this 20th day of August, 2003

UMATILLA COUNTY BOARD OF COMMISSIONERS

**ABSENT**

William S. Hansell, Chairman

*Emile M. Holeman*

Emile M. Holeman, Commissioner

*Dennis D. Doherty*

Dennis D. Doherty, Commissioner



ATTEST: OFFICE OF COUNTY RECORDS

By: *Jean Tompkins*  
Records Officer



APPROVED AS TO FORM:

*Doug Olsen*  
Doug Olsen, County Counsel



2003-4450519 3 of 3

State of Oregon )

County of Umatilla )

This instrument was received  
and recorded on

08-20-03 at 2:10

in the record of instrument  
code type DE-ORDER

Instrument Number 2003-4450519  
Fee 0.00

Office of County Records

  
Records Officer