

Field Notes of Road Survey No 287 for Umatilla Co. Oregon.

I meet viewers Wm. Steen, Wm. Bade and H. B. Lee at time and place appointed by the How. County Court for Umatilla County, Oregon and qualify them to act as viewers on Road Survey, No. 287, for the said County of Umatilla. I then call Chas. J. Winters and Jno. S. Sanders to carry the chain and Thos. H. Huntsberry to mark the road, and qualify each according to law.

I commence at a point on the line bet. Oregon and Washington ty. 5.50 chs. west of the intersection of said state line with the section line bet. Secs 14 & 15 in T. 6 N. R. 35 E.

		Set a split larch post, marked R on south side in mound 45 links west of point and run thence (var. $19^{\circ}30'E.$)
$30^{\circ}26'E$	10.63	Brook 12 lks. wide runs west - 5'
	11.63	Enter lane course N. & S.
	15.23	Irrigating ditch 5 lks wide runs N.W.
	17.63	Set angle stake 34 lks west of pt. at fence on W. side lane.
		Turn thence
$S20^{\circ}15'E$	34.38	Intersect said sec line bet. Secs. 14 & 15
		Set A on post in fence on E. side of lane 36 lks E. of point and turn on line bet said Secs 14 & 15
South	45.25	Spring branch, 10 links wide, runs west
	53.50	Ascend
	54.00	S. W. Cor. Sec. 14 T. 6 N. R. 35 E. W. M.

The viewers agreeing with me that it is impossible to reach S.E. Cor. said sec. 14 running south on line bet Secs 14 & 15 at this point we are compelled to throw up the sponge and adjourn sine die

I hereby certify the foregoing notes of the survey of County Road No. 287, for Umatilla County Oregon, are correct.

Jno. C. Arnold, Co. Surveyor.