

Field Notes of Road #538.

In accordance with an Order issued by the Honorable County Court of Muscatella County at their May term I went with C. W. Steer, David Still and H. B. Lee at Weston on the 10th day of June and after duly qualifying proceeded to the initial point of Road # 538, and did locate and survey said road as ordered.

We called to our aid Wm Jigman and L. O. Jeffys, who were duly qualified as chainmen, and C. E. Macomber acted as marker. Beginning at the 1/4 Section Corner to Sec 24 & 25.

Standard time

Local

P. C. P. M.
7⁵⁴ " "

Declination of Sun

23° 01' N

Altitude

60°

Latitude

45° 47' N

Variation of Needle

23° 10' E

Thence

S. 47° 55' E 1190 feet to south of beginning of Road. Where 30° E I marked P. in fence R. 538.

Field Notes Road #538

Course	Dist.	L	R	Total Dist
S 87° 40' E	2860 1900			1900
N 81° 40' E	312 207	10° 40'		2197
S 83° 31' E	200 133		14° 49'	2240
S 58° 12' E	206 137		25° 19'	2377
S 35° 18' E	333 221		22° 54'	2598
S 14° 27' E	680 450		20° 51'	3048
S 74° 08' E	1040 678	59° 41'		3726
S 36° 49' E	263 174		37° 49'	3900
N 80° 11' E	483 320	63° 30'		4220
S 49° 30' E	112 74		50° 29'	4294
S 34° 47' E	416 276		14° 43'	4570
S 29° 38' E	363 240		5° 09'	4810
S 32. 27' E	463 307	2° 49'		5117
S 20° 47' E	406 269		11° 40'	5386
S 3° 09' E	426 282		17° 38'	5668
S 38° 29' E	498 330	35° 20'		5998

Road 538 and intersection with County Road
 # Marked Pine tree 8" R.T. 538. 20 feet East
 of terminus.

L. E. Macomber
 County Surveyor.

I hereby certify that the foregoing is a
 true and correct copy of Field notes as
 made by me June 10, 1902.
 L. E. Macomber.