

FIELD NOTES OF COUNTY ROAD NO. 734


I commence at a point N.  $66^{\circ} 40'$  W. 21.72 Chs. distant from the center of Sec. 2 T. 5 N., R. 35 E., W. M.

At a point 20 ft. north of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 734: dug pits: 18 X 18 X 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence N.  $66^{\circ} 40'$  W. parallel with and 70 ft. from the center line of the O. W. R. & N. Co's. railway track 65.84 chs. to a point 230 ft. south of the N. W. corner of the N. E.  $1/4$  of section 3 in said township and range: thence north 12.65 chs.: thence north  $59^{\circ}$  W. 1.51 chs. to a point from which I set, to the left, 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1 M: dug pits, 18 X 18 X 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence N.  $59^{\circ}$  W. 45.62 Chs. distant to a point 6.60 Chs. S. of the N. W. corner of the S. W.,  $1/4$  of Sec. 34 T. 6 N., R. 35 E., W. M.: from which I set, 20 ft. N. & 20 ft. E. a post, 4 ft. long, 4 ins. square, marked R. T. 734: dug pits N. & E. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of County road No. 734 are correct, according to survey made by me, on the 18'th day of Feb. 1912.

  
Surveyor for Umatilla County, Oregon.