

Field Notes of Road Survey, made May 26th & 27th 1879
Monday May 26th 1879.

Met at the residence of D. Paylor. Monday May 26th 1879.
Present: Viewers. W. Hale & A. R. Price, who were duly
 Qualified, & after calling to my assistance & Qualifying the
 same according to law. Wm. Coving & W. H. Scott to act
 as chain bearers & D. Paylor to act as marker. Proceeded
 to Survey & Mark out what is known as the Old
Hundred Road

Cav: 21°

	Chain	Spikes	
			Set Stake in Mound as required by law at recog- nized Center of Section 23. P. 4. N. R. 34. E.
W	60		Set angle post in Mound in field on South side of travelled road. Post saved fir 4+4-2 1/2 marked A
N	80		Set post round tamarack Marked 1 M. + A. in flat near M. Kinsey's residence.
W	19 50		Set post. saved fir in Mound near D. Paylor's residence. Post Marked. A.
N	40 25		P. 4 Sec: Corner bet: Secs: 15 + 22 P. 4. N. R. 34. E.
N	80		Set post in lane, Mounded & Marked 11 N
N	40		P. 4 sec: Cor: bet: 10" + 15" Secs: P. 4. N. R. 34. E.
N	60		Set Stake saved on hill, in Mound. Marked A
W	80		Set Stake round fir. sq 4+4-3 1/2 in flat inside of field Post Mounded & Marked 111 N
W	5		Set post 4+4-2 1/2 in Mound. outside of field Marked A. Changed Course

	Com	f/100	
N. 21. W	80		Set round fir post of the proper dimensions in Mound Marked IV m. - in flat near J. H. Williams' house.
N. 21. W	80		Set post as req. by law. Mounded & Marked V m. in flat near traveled road at Davis place.
N. 21 W	80		Set post near Jas. M ^c Evans house mounded & according to law & Marked VI m.
N. 21. W	10		To the point of intersection with Sec. line bet. Secs: 28 + 29. P. S. N. R. 34. E. Changed Course. Set post for sawed 4 + 4 - 2 1/2. Mounded. Marked A.
N.	77		Along line bet. Secs: 28 + 29. to Cor Secs 20. 21. 28 + 29. P. S. N. R. 34. E.
N.	80		Set post according to law on each side Marked VII m
N 2 1/2 W	72		Along line bet. Secs: 20 + 21. to Cor Secs: 16, 17, 20 + 21. P. S. N. R. 34. E. Set 4 + 4 - 2 1/2. Sawed fir in Mound Marked A. Changed Course.
E	80		along line bet. Secs: 16 + 21. Set post according to law Marked VIII m. Mounded.
E	72	50	Along line bet. Secs: 16 + 21. to Cor Secs: 15, 16. 21 + 22. P. S. N. R. 34. E.
E	80		Along line bet. Secs: 15 + 22. Set stakes in Mound. According to law. Mounded Marked IX m.
E	80		Along line bet. Secs: 15 + 22. + Secs: 14 + 23. P. S. N. R. 34. E. Set post according to law near traveled road Mounded & Marked X m
E	58	88	Set terminal post on east hill side in plowed ground Mounded & Marked "B."

J. H. Raley Surveyor
Per John C. Arnold
Deputy