

FIELD NOTES OF COUNTY ROAD NO. 735.

I commence at the corner of sections 29, 30, 31 & 32, T. 4 N., R. 35 E., W. M. At a point 25 ft. N. and 25 ft. W. of aforesaid point I set a post, 4 ft. long, 4 ins. square, marked R. 735: dug pits, 18 x 18 x 12 ins., N. and W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the line between sections 31 & 32 south 80.00 chs. to a point from which I set to the right, 25 ft. distant a post, 4 ft. long, 4 ins. square, marked 1 M: dug pits, 18 x 18 x 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the line between sections 5 & 6 in T. 3 N., R. 35 E., W. M., south 160.00 chs. to a point from which I set, to the right, 25 ft. distant, a post, 4 ft. long, 4 ins. square, marked 2 M: dug pits, 18 x 18 x 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the line between sections 7 & 8 in said last named township and range, south 240.00 chs. to a point from which I set, to the right, 25 ft. distant, a post, 4 ft. long, 4 ins. square, marked 3 M: dug pits, 18 x 18 x 12 ins., N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the line between sections 17 & 18 in said township and range, south 275.00 chs. to a dry slough, 20 links wide, course east: thence south 283.70 chs. to foot of steep hill.

Thence continuing south 332.10 chs., a point from which I set, N. 25 ft. & W. 25 ft., a post, 4 ft. long, 4 ins. square, marked R. T. 735: dug pits N. & S. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.



I hereby certify that the foregoing field notes of  
County road No. 735 are correct, according to survey made by me on  
the 1'st day of March 1912.

Geary Kimbell  
Surveyor for Umatilla County, Oregon.