

464

Field Notes of Road Survey No. 386, for Umatilla County Oregon.

I meet A. R. Price, S. P. Purdy and Tho. Page, pr., viewers on R. no. 386 at Athena Monday Feby 22nd 1892 and administer usual R. V. oath to each. - We call J. C. Still and Edgar Thomson to chain and mark, each of whom duly made oath as required by law. - On arriving at vicinity of beginning of said road, I am required to find center of $\frac{1}{4}$ of Sec 24 T. 4 N. R. 34 E. I therefore, according to law for the same, set $\frac{1}{4}$ S. cor. bet. secs. 13 + 24; and secs. 23 + 24; after which I set at intersection of center lines N. + S. and E. + W., the center of said sec. 24. Believing that the $\frac{1}{16}$ S. cor., or center of $\frac{1}{2}$ of line E. + W. through center of said sec. 24 to be the true initial point of Road 386, instead of center of S. E. $\frac{1}{4}$ of sec. 24, I am instructed to find this point, which I do and place a stone at each point found so as to perpetuate the corners.

I set initial post to R. 386 against fence on N. side of lane course E. + W. and 42 lks. N. of stone $\frac{1}{16}$ sec. cor. on $\frac{1}{2}$ of line E. + W. through center sec. 24 T. 4. N. R. 34 E.

thence I run South $va. 20^{\circ} 30' E.$ Descend.

0.58	Center of Rail fence on S. side of lane, at a point 20 lks west of cor. of fences S. + W. on W. side of intersection of old lane South, now closed and plowed up. I mark pts. of intersection.
16.00	Foot of hill
19.75	Wild Horse Creek 25 lks. wide, runs west bridged.
29.30	Ditch 20 lks. wide, course west bridged.
31.10	A point 120 lks. N. of center of R. R. track

Set a. p. 1 and turn $R 60^{\circ} 30'$ along N. side of R. R. R. of way.

S. $60^{\circ} 30' W.$	49.55	" " 2 " " " L $2^{\circ} 50'$ " " " " "
S. $57^{\circ} 40' W.$	76.60	" " 3 " " " L $12^{\circ} 15'$ " " " " "
S. $45^{\circ} 25' W.$	80.00	cut 1 M on S. side of split fir post in fence, course N. E. + S. W. Raised a mound of earth 3 ft. h. x 4 ft. b. around the post, which = 4×4
S. $43^{\circ} 25' W.$	13.36	Set a. p. 4 and turn S. 2° along N. side of R. R. R. of way.
	26.24	" " 5 " " " L $43^{\circ} 25'$ or South

South	27.59	Center of R. R. track, bears N.E. + S.W.	
	28.62	Wire fence, bears E. + W.	
	30.79	The 1/4 Sec. cor. bet. sec. 25 + 26. I cut A on N. side of Cedar post in cor fence S. + E. + W. and turn S. 180° or North	Corder.
North	32.96	Wire fence bears E. + W.	
	35.35	A. p. no 5, also no. 6, and turn S. 136.35	
S. 43° 25' W	43.25	Set a p. 7. center of intersection of lane, course W. At this point, I am directed to find center of sec. 26, which I do according to law for the same, establishing stone corners where necessary. I then turn R 43° 30' from a. p. 7	
	69.50	Wild Horse creek 50 lks. wide, course S.W. - bridged 105 lks.	
S 88° 55' W	78.30	The stone center cor. to sec. 26 T. 4 N. R. 34 E. I set terminus 52 lks. N. of cor., against fence on S. side of lane E. + W. - All the posts are of size, and marked and set in mounds as required by law.	
I hereby certify that the foregoing are the correct notes of Road Survey 386.		Jno. C. Arnold, Surveyor. Umatilla Co. Oregon.	

Field Notes

Road Survey 386.

FILED MAR 10 1892
 W. M. Pierce Clerk