

## Field Notes of Road Survey No. 371, for Umatilla County, Oregon.

Wednesday, Aug. 26<sup>th</sup> 1891, I meet J. M. Watson and R. G. Thompson, who had, by the Co. Clerk, been sworn in as viewers on Road Survey 371. We called Dude Frazier, Wm. Surrall and Isaac W. Kimball to chain and mark, and administered oath to each.

I set initial post on R. 371, 30' East of the intersection of the baseline with the line bet. ranges 32 & 33 E. and with Engineer's transit. I run from said point of intersection, along said range line

North	2650	The $\frac{1}{4}$ sec. cor. bet. secs 31 & 36.
	5280	Set 1 m. p. 30' E. Rout good.
	1000	Cor. for secs. 25, 26, 30, 31
	4500	Set angle post 1 and turn, thence,
75° 56' E	7000	Descend to creek, course N 45° E - Some water - Fair grade to creek.
	1110	Set a. p. 2; thence, gradual ascent - Loose rock - Needs grading.
258° 51' W	1874	Intersect line bet. secs 25 & 30. Set a. p. 3; thence on Range line
North	5280	Set 2 m. p. 30' E. Sand level; fenced on W.
	1400	Sec. cor. for secs. 19, 24, 25 & 30.
	2300	Set a. p. 4. Leave Range line, and turn, thence,
784° 40' E.	2673	" " 5
764° 37' W.	3072	Intersect line bet. ranges 32 & 33 E. Rout steep - Loose rock - Needs grading. Set a. p. 6, and turn, thence,
North	4040	The $\frac{1}{4}$ sec. cor. bet. secs 19 & 24.
	5280	Set 3 m. p. 30' E.
	1500	Cor. for secs. 13-18-19-24.
	3240	Ravine, runs West - Ascent steep.
	3600	Summit - Level.
	4150	The $\frac{1}{4}$ sec. cor. bet. secs. 13 & 18.
	5075	Foot of gradual ascent - Loose rock.
	5280	Set 4 m. p. 30' E. + 250 to summit - Level.
	1516	Cor. for secs. 7, 12, 13, 18.
	4182	The $\frac{1}{4}$ sec. cor. bet. secs. 7 & 12.
	5280	Set 5 m. p. 30' E. Ground level.
	1525	Cor. for secs. 1-6-7-12 at + 2350 Road + ing N.W. & S.E.
	4000	Ravine N.W. needs culvert.
	4164	The $\frac{1}{4}$ sec. cor. bet. secs. 1 & 6.
	5280	Set 6 m. p. 30' E. - Ground level.
	1525	Cor. for Tps. 1 & 2 N. Rgs. 32 & 33 E.
	3700	Ravine, course W. Needs bridge 15' long.
	4240	The $\frac{1}{4}$ sec. cor. bet. secs. 31 & 36.
	5280	Set 7 m. p. 30' E.
	1610	Cor. for secs. 25-30-31-36.
	2750	Foot of hill - Ascend gently to 3100 Summit.

	5280	Set 8 m. p. 30 E. House bears N.W. 200 dist.
	1635	Cor. for secs. 19-24-25-30.
	4300	The 1/4 sec. cor. bet secs. 19 & 24 - Summit.
	5280	Set 9 m. p. 30 E. - Easy descent to Tudor Willow Creek.
	1680	Cor. for secs. 13-18-19-24.
	4300	Tudor Willow Creek, runs W. Needs 30 bridge.
	5280	Set 10 m. p. 30 E. + Set a. p. 6, and turn thence,
N. 28° 04' E.	400	Set a. p. 7 - steep hill,
N 36° 11' W	740	Intersect line bet. secs 17 & 18. - Set a. p. 8; thence on sec. line.
North	1850	Cor. for secs. 7-12-13-18. - Set a. p. 9, and turn thence,
West	2000	Set a. p. 10 " " "
N 51° 15' W.	2300	" " 11 " " "
S 38° 36' W.	3043	" " 12 " " "
- West	4660	The 1/4 sec. cor. bet. secs. 12 & 13. - Set a. p. 13; thence through 12.
North	5280	Set 11 m. p. 30 E.
"	2055	Center sec. 12 - Set a. p. 14, and turn thence,
West	4750	The 1/4 sec. cor. bet. secs. 11 & 12 - Set a. p. 15,
"	5160	Set a. p. 15, and turn thence,
N 21° 00' W.	5280	" 12 m. p. 30 E.
	820	Int. body line of Pendleton

Set terminus 30'

All the posts are of the size, and marked and set in mounds, as required by law.

I hereby certify that the foregoing are the correct notes of Road Survey No. 371, for Clatsop Co. Oregon.

Jno. H. Arnold, Co. Surveyor.

Field Notes of  
Road Survey 371.

FILED SEP 8 1891

W. M. Green, Clerk  
Deputy

4660  
3043  
1617