

Field Notes of Road Survey No. 394, for Umatilla County Or.

I find myself at Meacham June 13th, 1892, at 7 a. m. pursuant to order of the county court for, Umatilla Co., Or. - I should have stated that Meacham is situated in said county and state. - Finding no viewers on hand, nor any particular excitement in regard to the road to be surveyed, I had almost made up my mind to "fold my tent and silently wend my way homeward, when a thought came over me, that I might hunt down the viewers on road survey No. 394, as I have so frequently done before. I arrive at Res. of S. P. Stouser at 7 1/2 a. m. but to find Mr. St. gone to the Res. of Robt. Murdock; to the latter place, I arrive, after footing my way over hills and fall in trees, and stumps and roughest of roads, about 8 a. m. and find that messrs. Stouser and Murdock had, some half hour previous, set out for Murdock's Mill. - Nerved to succeed or perish in the attempt, I again set out, over roads as described, and about 8:30 a. m. being in a state of mind bordering upon desperation, I find these two gentlemen at the latter named place. From them I learn that one viewer, R. St. McKee, had left the country, and nothing known of the whereabouts of St. W. Cuthbert. I send S. P. Stouser to Meacham, to await incoming train from Kamela, and, in case Mr. Cuthbert does not appear, to dispatch telegram, as follows: -

"St. W. Cuthbert - Kamela - Or.

You are required to appear at Meacham, forthwith, as road viewer, No. 394, and to show cause why you should not be electrocuted for contempt of the Hon. County Court for Umatilla County Oregon.

Dated June 13th 92 at Meacham, Oregon.

Jno. C. Arnold, County Surveyor."

Mr. Cuthbert immediately came, and, by way of excuse said he thought Road 394 was set for June 16th.

I stiffly swore in S. P. Stouser and St. W. Cuthbert viewers on said road 394, and a sufficient number of assistants to chain, mark and cut brush, and immediately proceed with the survey of said road. I find a point in traveled road course N.E. & S.W. 664 links north of the 1/4 sec. cor. bet. secs. 15 & 22 T. 1 S. R. 35 E, which I take for the initial point of survey, and from which a fir

Course
N49:15'E

Dist	Turns	Remarks
18 ins.		dia bears N. 74° W. 18 lks. dist, marked R 394. 0 on E., for initial post, Thence I run, from initial point
11.00	L	Along traveled road, - Enter dense brush.
16.56	R 22:30	Set angle post mkd. 1.
27.70	L 21:08	" a. p. mkd. 2.
30.71	R 42:05	" " " 3
33.78	R 14:30	" " " 4
41.30	L 24:30	" " " 5
43.43	R 20:15	" " " 6, at upper edge of grade. - leave brush. Descend steep grade.
48.60	R 22:35	" " " 7, on line, and cut 7 on post 30 lks N. of line
49.50		Murdock's Mill house bears S. about 75 lks
51.00		Saw Mill bears N. 150 lks. dist.
51.50		Meacham creek 15 lks. wide, runs N.
52.00		Ascend hill, E. side of creek.
52.70	L 71:55	" " " 8
54.97		The 1/4 sec. cor. bet. secs. 14. & 15.
60.66		" " " 9 on W. side of R.R. track, on line and cut 9 on stake 30 lks. N. of line.
61.83		R. R. track, nearly N. & S.
62.21	R 13:13	Set a. p. mkd. 10, on line, and stake mkd. 10, 30 lks. N. of line.
64.00		Enter dense timber.
74.25	L 13:18	Set a. p. mkd. 11, on summit - Descend.
78.50		Ravine runs W. - leave brush & timber. ^{ascend}
80.00		A fir 8 ins. dia. bears E. of line 62 lks. dist. mkd. 11M; drive stake on line, marked 11M
3.00		Summit. Descend gently.
5.68	L 22:30	Set a. p. mkd. 12
14.50		Enter dense brush.
17.50		Ravine runs N.W. - Ascend.
19.00		Leave brush
23.50	L 87:30	" " " 13 in stone md. on open ground, at int. ^{of trav. road}
63.00		Along old stage road. Descend gently.
63.00		S.P. Houser's house bears west about 5 chs. dist.
68.11	L 21:50	Set a. p. mkd. 14
79.47	R 16:35	" " " 15
79.80		A fir 10 ins. dia. bears E. of line, 60 lks. dist. mkd. 11M
11.95	L 6:05	Set a. p. mkd. 16
19.50		The 1/4 sec. cor. bet. secs. 2 & 11 bears west 304 lks. dist.

21.00	R 8° 00'	Set a. p. mkd. 17
38.00		School house, bears west about 3 ch.
47.38	R 15° 18'	" " " 18
62.65		True terminus of R. Survey No 377. bears west 65 lks., and north 45 lks. dist.
80.00		" 3 m. p. 38 lks. E. of line.
4.90	L 32° 55'	But 19 on post in fence 16 lks. E. of line, at E. end of bridge across Meacham creek, 60 lks. long.
15.20		Center of R. R. track course about
17.26		Center of King David's street in town of Jerusalem, now called Meacham. - This point is at inter- section of centers of King David's street and King's Highway in said town. I set a. p. mkd 20.
		a large round post and turn along center of King's Highway, on line 30 ft E. of the west line of said highway.
27.75		But R 394 on stump 24" dia. and 26 lks. N. of N end of King's Highway, to mark term- inus of Road Survey No. 394.

All the posts are of the size, and are marked and set in mounds as required by law for the same.

I hereby certify that the foregoing are the correct field notes of Road Survey No. 394, for Ematilla County, Oregon.
Jno. C. Arnold, Surveyor.