

**IN THE BOARD OF COUNTY COMMISSIONERS OF UMATILLA COUNTY**

RECEIVED

**STATE OF OREGON**

NOV 12 1996

1:30 PM  
UMATILLA COUNTY  
RECORDS

**IN THE MATTER OF LEGALIZATION )  
OF A PORTION OF SHAW ROAD, )  
COUNTY ROAD NO. 1061 )**

**ORDER NO.** RD96-10

**WHEREAS**, the Umatilla County Board of Commissioners may, under authority of ORS 368.201 to 368.221, order a county road that has been used and traveled by the public for ten (10) years or more to be surveyed and recorded, and

**WHEREAS**, the Umatilla County Board of Commissioners ordered the survey of that portion of Shaw Road (County Road No. 1061) described as follows:

A strip of land for road purposes located in the Southeast  $\frac{1}{4}$  of Section 35, Township 1 North, Range 32 East W. M. and in the Northeast  $\frac{1}{4}$  of Section 2 and the Northwest  $\frac{1}{4}$  of Section 1, Township 1 South, Range 32 East W. M., said parcel being 40 feet in width and lying 20 feet on each side of the following described centerline:

Commencing at a brass-capped monument marking the closing corner common to Sections 1 & 2 in Township 1 South, Range 32 East W.M. and Section 35, Township 1 North, Range 32 East W.M.; Thence  $N70^{\circ}22'51''$  W, 773.81 feet to a 5/8-inch iron pin and the true point of beginning of this description, said point being assigned engineer's station 100+00.00; Thence  $S0^{\circ}19'12''$ E, 217.68 feet; Thence 70.35 feet along a 44.42 foot radius curve left ( The long chord bears  $S45^{\circ}41'30''$  E, 63.23 feet); Thence  $N88^{\circ}56'12''$ E, 289.62 feet; Thence 231.47 feet along a 179.43-foot radius curve right ( the long chord bears  $S54^{\circ}06'23''$ E, 215.75 feet ); Thence  $S17^{\circ}08'59''$ E, 589.59 feet; Thence 178.74 feet along a 617.36-foot radius curve right ( The long chord bears  $S8^{\circ}51'19''$ E, 178.12 feet); Thence  $S0^{\circ}33'40''$ E, 453.02 feet to a 5/8-inch iron pin marking the North  $\frac{1}{16}^{\text{th}}$  corner common to Sections 1 and 2, Township 1 South, Range 32 East W.M. and there terminating, said point being assigned engineer's station 120+30.47.

**WHEREAS**, the Notice of Hearing was posted and all owners of abutting property affected by the legalization procedure were served copies of the Notice of Hearing, and

**WHEREAS**, the Umatilla County Board of Commissioners on November 6, 1996, held a public hearing and received no objections to the legalization:

**THEREFORE IT IS NOW ORDERED** that the survey of Shaw Road, County Road No. 1061, be recorded by the County Surveyor, and that the road be legalized as described above.

Dated this 6<sup>th</sup> day of November, 1996

UMATILLA COUNTY BOARD OF COMMISSIONERS

  
Emile Holeman, Chairman

  
Glenn Youngman, Commissioner

  
William S. Hansell, Commissioner




ATTEST: OFFICE OF COUNTY RECORDS

By:   
Records Officer



APPROVED AS TO FORM:

  
William Jones, County Counsel