

# UMATILLA COUNTY, OREGON

## FIELD NOTES

County..... Road No. 871.....

Date ..... 1927.....

STATION	Curve Data	Length of Tangents and Curves	Bearing	REMARKS
0+00 P.C.	40° C.L.			Beginning of project, which point is in the center of County Road No. 531, 517 feet North and 636.7 feet West of the Quarter Section corner common to sections land 12 T.1 S., R. 32 E. W. M.
1+87.5 P.T.	Δ=75°02'	187.5		
		607.7	S. 21° 07' W.	
7+95.2 P.C.	10° C.R.	207.3		
10+02.5 P.T.	Δ=20°44'			
		434.6	S. 41° 51' W.	
14+37.1 P.C.	10° C.L.	205.8		
16+42.9 P.T.	Δ=20°35'			
		621.7	S. 21° 16' W.	
22+64.6 P.C.	10° C.R.	317.0		
25+81.6 P.T.	Δ=31°42'			
		210.0	S. 52° 58' W.	
27+91.6 P.C.	4° C.L.	439.6		
32+31.2 P.T.	Δ=17°35'			
		188.0	S. 35° 23' W.	
34+19.2 P.C.	8° C.L.	407.1		
38+26.3 P.T.	Δ=32°34'			
		2876.3	S. 2° 49' W.	End of project, which point is in the center of County Road No. 438, 572.5 feet South of the Quarter Section corner common to sections 11 and 12, T.1 S., R. 32 E. W. M.