

WATILLA COUNTY, OREGON

FIELD NOTES

County..... Road No. 867.....

Date Oct 1926.....

STATION	Curve Data	Length of Tangents and Curves	Bearing	REMARKS
0+00		10.8	East	Beginning of Project, which point is coincident with the Quarter Corner Common to sections 12 and 13 T.4N, R.28E. W.M.
0+10.8	11° C.L. Δ=25°47'	234.4		
2+45.2 P.T.		2676.8	N.64°13'E.	
29+22.0 P.O.T.		684.0	N.64°13'E.	Which point is on the Range line between Range 28 and 29 T.4N.
36+06.0 P.C.	1° C.R. Δ=7°52'	786.7		
43+92.7 P.T.		1924.2	N.72°05'E	
63+16.9 P.O.T.		2762.9	N.72°05'E.	Which point is 268.2 feet South of the Center of Section 7 T.4N, R.29 E.W.M.
90+79.8 P.O.T.		1817.3	N.72°05'E.	Which point is on the section line common to Section 7 and 8
108+97.1 P.C.	10° C.R. Δ=16°43'	167.2		
110+64.3 P.T.		3199.0	N.88°48'E.	
142+63.3 P.C.	4° C.L. Δ=10°54'	272.5		P.O.S.T. 104.6 From Pl. Ahead to a point on the section line 1586.5 feet South of the Section Corner Common to sections 4, 5, 8 and 9.
145+35.8 P.T.		1162.9	N.77°54'E.	
156+98.7 P.C.	4° C.R. Δ=10°49'	270.4		
159+69.1 P.T.		1206.8	N.88°43'E.	
171+75.9 P.O.T.		2273.4	N.88°43'E.	Which point is coincident with the 1/16 Section corner 1/4 Mile North of the Center of Section 9.
194+49.3 P.C.	4° C.L. Δ=24°36'	615.0		
200+64.3 P.T.		29.3	N.64°07'E.	
208+93.6 P.C.	6° C.R. Δ=14°15'	237.5		
203+31.1 P.T.		953.8	N.78°22'E.	
212+84.9 P.C.	40° C.R. Δ=68°12'	170.5		
214+55.4 P.T.		226.7	S.33°26'E.	
216+82.1 P.C.	20° C.L. Δ=57°41'	288.4		
219+70.5 P.T.		3307.5	N.88°53'E.	
252+78.0 P.I.	Δ=0°19' Rt.	2655.1	N.89°12'E.	Which point is on the section line Common to sections 10 and 11

