

FIELD NOTES OF COUNTY ROAD NO. 714.

I commence at the 1/4 Sec. corner between Secs. 27 & 28 T. 5 N., R. 29 E., W. M. At a point 20 ft. S. and 25 ft. W. from aforesaid point, I set a post, 4 ft. long, 4 ins. square, marked R. 714; dug pits, 18 x 18 x 12 ins., S. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the subdivisinal section line west 15.00 chs. to irrigation ditch 10 lks. wide course N. 53.40 ,, ,, ditch, course N. W. 74.10 ,, ,, ,, 10 lks. wide, 80.00 chs. to a point from which I set, to the left, 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 1M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the subdivisinal section line west 160.00 chs. to a point from which I set to the left, 20 ft. distant, a post, 4 ft. long, 4 ins. square, marked 2 M; dug pits, 18 x 18 x 12 ins., E. & W. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

Thence following the subdivisinal section line west 241.60 chs. to the 1/4 section corner on the west side of Sec. 30 in said township and range from which I set, 20 ft. S. & 30 ft. E. a post, 4 ft. long, 4 ins. square, marked R. T. 714; dug pits S. & E. of post, and raised mound of earth, 18 ins. high, 4 ft. base, around post.

I hereby certify that the foregoing field notes of County road No. 714 are correct as surveyed by me on the 25'th day of May, 1911.

Geary Kimbell

Surveyor for Umatilla County, Oregon.