



1999-3560419 1 of 2

RECEIVED

AUG 20 1999

UMATILLA COUNTY

IN THE BOARD OF COUNTY COMMISSIONERS OF UMATILLA COUNTY

- 356 0419 STATE OF OREGON

IN THE MATTER OF LEGALIZATION)
OF A PORTION OF RIETH ROAD,)
COUNTY ROAD #1300)

ORDER NO. RD 99-09

WHEREAS, the Umatilla County Board of Commissioners may, under authority of ORS 368.201 to 368.221, order a county road that has been used and traveled by the public for ten (10) years or more to be surveyed and recorded, and

WHEREAS, the Umatilla County Board of Commissioners ordered the survey of a portion of Rieth Road (County Road #1300) lying between Interstate 84 and Rieth, and

WHEREAS, the Notice of Hearing was posted and all owners of abutting property affected by the legalization procedure were served copies of the Notice of Hearing, and

WHEREAS, the Umatilla County Board of Commissioners on August 18, 1999, held a public hearing and finding that it would be in the public interest to legalize the road:

THEREFORE IT IS NOW ORDERED that the road be legalized as follows:

A strip of land for road purposes being 60 feet in width and lying 30 feet on each side of the following described centerline:

Beginning at a brass cap marking the intersection of the centerlines of Main Street (Rieth Road) and Morrow Street, as shown on the Plat of the Town of Doris, which bears S54°47'04"W, 2678.29 feet from a brass cap marking the Center of Section 7, Township 2 North, Range 32 East of the Willamette Meridian, said monument being assigned Engineer's Station 100+00.00 P.O.T.; thence N55°49'40"E, 80.52 feet; thence 231.69 feet along a 1500.00-foot radius curve right (the chord bears N60°15'10"E, 231.46 feet); thence N64°40'40"E, 176.93 feet; thence 157.49 feet along an 800.00-foot radius curve left (the chord bears N59°02'18"E, 157.23 feet); thence N53°23'55"E, 370.02 feet; thence 70.92 feet along a 716.20-foot radius curve right (the chord bears N56°14'07"E, 70.89 feet); thence N59°04'19"E, 593.82 feet; thence 68.93 feet along a 572.96-foot radius curve right (the chord bears N62°31'06"E, 68.88 feet); thence N65°57'52"E, 545.56 feet; thence 423.42 feet along an 1130.00-foot radius curve left (the chord bears N55°13'48"E, 420.95 feet); thence 179.52 feet along a 471.32-foot radius curve right (the chord bears N55°24'26"E, 178.44 feet); thence N66°19'08"E, 248.75 feet; thence 366.80 feet along a 1600.00-foot radius curve left (the chord bears N59°45'05"E, 366.00 feet); thence N53°11'02"E, 229.52 feet; thence 67.77 feet along a 460.00-foot radius curve right (the chord bears N57°24'16"E, 67.71 feet); thence N61°37'29"E, 105.73 feet; thence 208.94 feet along an 8645.26-foot radius curve left (the chord bears N60°55'57"E, 208.93 feet); thence 500.00 feet along a spiral curve left (a=1.0, S=12°30'00", chord bears N56°04'30"E, 498.94 feet); thence 564.67 feet along an 1145.92-foot radius curve left (the chord bears N33°37'24"E, 558.98 feet); thence 500.00 feet along a spiral curve left (a=1.0, S=12°30'00", chord



1999-3560419 2 of 2

Order No. RD 99-09 Page 2

bears N11°10'17"E, 498.94 feet); thence N07°00'23"E, 182.86 feet; thence 400.00 feet along a spiral curve right (a=2.0, S=16°00'00", chord bears N12°20'10"E, 398.62 feet); thence 400.00 feet along a 716.20-foot radius curve right (the chord bears N39°00'23"E, 394.82 feet); thence 41.76 feet along a spiral segment right (a=2.0, S=3°09'54", chord bears N56°37'07"E, 41.75 feet) to a point on the Umatilla County/Oregon Department of Transportation jurisdiction boundary line. Said point bears N67°02'32"W, 139.12 feet from a brass cap marking the Northeast Corner of Section 7, Township 2 North, Range 32 East of the Willamette Meridian, is assigned Engineer's Station 167+15.61 P.O.S., and is the terminus of this description.

Dated this 18th day of August, 1999

UMATILLA COUNTY BOARD OF COMMISSIONERS

Emile M. Holeman
Emile Holeman, Chairman

ABSENT


Dennis Doherty, Commissioner

William S. Hansell
William S. Hansell, Commissioner



APPROVED AS TO FORM:

By: [Signature]
DOUG OLSEN, COUNTY COUNSEL



ATTEST: OFFICE OF COUNTY RECORDS

BY: [Signature]
RECORDS OFFICER

State of Oregon)
County of Umatilla)

This instrument was received and recorded on 08-20-99 at 9:27

in the record of document code type DE-ORDER

Location R356-0419
Document number 1999-3560419
Fee 0.00

Office of County Records

[Signature]
Records Officer