

County Road No. 570

570

I Commenced at the $\frac{1}{4}$ sec cor. bet Secs 11 and 14
 in Township 2 N 16 31 6 W m set Stone 20x8x7 inches
 at Exact-corner point - marked $\frac{1}{4}$ on south side and
 marked B 570 on post 20 feet North of Initial Point
 dug pits N and S and made mound of Earth 18 ins high
 4 ft wide at Post Hence I run

East on line bet Secs 11 and 14	2400 chains	A 1	
Hence N 63° 30' E	533 chains	2933 "	A 2
Hence N 82° E	300 "	3233 "	A 3
Hence N 86° E	610 "	3843 "	A 4
Hence N 46° E	260 "	4103 "	A 5
Hence S 70° E	410 "	4513 "	A 6
Hence S 42° E	723 "	5236 "	A 7
Hence S 61° E	1030 "	6266 "	A 8
Hence S 71° 30' E	530 "	6796 "	A 9
Hence East	320 "	7116 "	A 10
Hence N 87° E	360 "	7476 "	A 11
Hence N 70° E	297 "	7773 "	A 12
Hence N 49° E	146 "	7919 "	A 13
Hence S 60° E	81 "	8000 "	1 mile A 14

Set Post 4 ft long 4 ins square Marked I.M. dug pits N and S
 and made mound of Earth 18 ins high 4 ft wide at base.

from White to $\frac{1}{4}$ sec cor bet Secs 12 and 13 Secs N 39° E 857⁵⁶⁶ 1/2 mile

Hence S 39° 30' W	462 chains		
Hence S 14° E	175 "	637 chains	A 15
Hence N 76° E	1180 "	1817 "	A 16
Hence N 60° E	415 "	2232 "	A 17
Hence N 42° E	960 "	3192 "	A 18
Hence N 71° E	900 "	4092 "	A 19

670

Thence S 80° E	615	"	47.07	"	A 20
Thence S 46° E	¹⁰⁶ 325	"	50.32	"	A 21
Thence S 78° E	²¹⁴ 105	"	51.37	"	A 22
Thence S 87° E	⁶⁹ 440	"	55.77	"	A 23
Thence N 52° E	²⁹⁹ 367	"	59.44	"	A 24
Thence N 40° E	²⁴² 662	"	66.06	"	A 25-
Thence N 53° E	⁴³⁷ 987	"	75.93	"	R.T. at AN
	^{651 1/2}				

of County Road No

Marked Post S 40° W 45 feet dist R.T. No 570 dig pits West and South and made mound of earth 18 in high 4 ft wide at base

I hereby certify that the above are correct field notes of
 Road Survey No 570 as surveyed by me on the 13th day
 of April 1905

John W. Kimbrell County Surveyor
 for Washtenaw County, Oregon

Field Notes of
 Road No. 570