

Field Notes of Road Survey No. 342 for Imatilla Co. Oregon

I met Francis Konasek and O. W. Fee, viewers on Road Survey No. 342, at Lee's crossing of Birch Creek, on Friday August 1<sup>st</sup> A.D. 1890, and administer oath to each.

We call Edgar Thomson and Henry Thomson to chain and mark and Allan Rhodes axeman, each of whom were sworn according to law.

I commence at Old road post, near head of grade on W. side of crossing of <sup>lower</sup> Mibay creek: said post marked M1 on W. face. I mark R on South face and repair mound about same, for initial post on road No. 342.

Run thence var. 20° E.

S. 17° 15' W	1100	Descend along traveled road to Birch creek.
1544	1317	Set angle post and turn, thence Right 41° 33'
	2644	Set angle post and turn thence
S. 58° 48' W	3224	" " " " " " " " " " " "
S. 47° 38' W	3344	" " " " " " " " " " " "
S. 12° 38' W	3750	Ditch runs west, 5' deep & 6' wide
597 ft	3900	Foot of hill
	3941	Old well on line
		Reputed center sec. 29 T. 2 N. R. 32 E.
		Set angle post and turn on reputed center sec line
South	4112	Wire fence E + W.
	4500	Enter dense brush on N. side of Birch creek in bottom.
	4700	Set angle post by fence N. & S. and turn, thence,
S. 53° 24' W	4757	East bank of Birch Creek } course N. W.
	4807	West " }
	4830	Set angle post in brushy flat and turn thence
S. 23° 24' W	4905	Precipitous bank - W. side Birch creek - Ascend.
	4936	cut A on post in wire fence and turn thence
S. 41° 16' E	5280	Set 1 mile post 30' west of line

Friday August 1<sup>st</sup> 1890.

Continue course

South	111	Intersect N. & S. line through center sec. 29. Set angle post by N. & S. fence, and turn thence along center sec. line
	196	Gulch 4' wide, runs East
	392	N. side of gulch 6' deep & 8' wide, runs N. E.
	650	Gulch 40' wide N. E. & N. Ascend



342

South	1488	1/4 Sec. cor. bet. sees. 30 & 31. Cut A on post in cor. fences N. & W. - Summit
		Turn thence, Descend
S. 62° 16' W.	2090	Gulch 2' wide runs N. E.
	2117	Set angle post and turn
S 80° 30' W.	2486	Rocky Ravine runs S. E.
	2562	Set angle post and turn thence
N. 15° W	2950	Summit, set angle post and turn thence
West	5280	Set 2 mile post 30' south of line.
	685	Draw runs N.
	1413	Cut A on Cor. post in fences E. & W. and turn, thence,
S. 26° 30' W.	1780	Gulch 4' deep, & 15' wide runs N. W.
	1985	Washout 3' deep & 4' wide do.
	2302	Cut A on post in fence N. & S. and about 300' South of 1/4 S. cor. bet. sees. 30 & 31. and turn, thence
South	2931	Set angle post and turn, thence,
S. 26° 18' W.	3171	
S 23° 07' E	3495	Int. line N. & S. through center sec. 31 Set angle post and turn thence, along center Sec.
South	3800	Summit
	3850	Descend
	4034	Gulch N. W. to N. Ascend.
	4553	Summit
	4628	Draw runs west
	4728	Summit - 4895 descend.
	4945	Ravine runs S. W. Ascend.
	5045	Summit - descend.
	5133	Gulch, course west Ascend.
	5280	Set 3 m. p. 30' west of line
	300	Summit
	1200	Ascend gently
	1957	South end of washout 15' deep course N. E. & N.
	2500	Alkali gulch N. E. & N.
	2834	Fence runs west
	4154	Cut A on West side of post in cor. fences N. & E. on summit = center sec. 6. Turn thence
S 26° 24' W	5280	Set 4 m. p. 30' west of line
	1813	Cor for 16 sec W 1/2 of line bet sees. 6 & 7



		cut A on post in fence E + W. on S side of lane, west and turn thence, enter lane, ascend
West	2100	Summit
	5280	Set 5 m. P. 30' south of line.
	1000	Set angle post by fence on south side of lane and turn
S. 69° 15' W.	1350	Descend to Combs Cañon.
	2100	Guleh runs west
	2350	Fence on E side of N + S. lane - Foot of hill.
	2402	" " W. " " " " " " " "
	2719	Guleh 10 deep course N. ascend over point
	3250	Summit - Descend
	3450	Foot of descent.
	3731	Cor. fences S. + W. - Cut A on west side of cor. post and turn, thence, along road in lane
N. 88° 58' W.	4150	cut A on south side of post in cor. fences E. + N. and turn thence
S. 49° 52' W.	5250	cut VIM on south side of basalt stone in place on N. side of traveled road and 33' N. of line.
	40' 4	Set angle post on N. side of trav. road and turn, thence,
S. 61° 42' W.	1500	cross wire fence
	1719	" " " same fence, making angle about 120°
	1738	Set angle post and turn thence
S. 82° 47' W.	2600	" " " " " "
S. 77° 00' W.	4400	" terminus 30' north of line
	6,833 M. es	

Saturday Aug 2<sup>nd</sup> 1890. -

I hereby certify that the foregoing are the true field  
notes of Road Survey No. 342. for Umatilla County Oregon.  
Geo. C. Arnold, Surveyor.