

Field No, 745

Commencing at the S,E, Corner of the S.W.1/4 of the S,W,1/4 Section 21,
T,1,N,R,32,E,W,M, Set post 4 x 4 ins,4 feet long Marked R,No,745 made
mound 4 feet Base and 18 inches high around post,

Thence East 7.00 spring branch

9.00A,1

Thence S,11°E, 4,05 chs, 13,05,..... A,2

.. S,51°E, 1,45 14,50.....A.3

.. N.65°30'E,2,48 16,98.....A.4

.. N,47°15'E,5,70 22,68.....A,5

.. East 57.32.....80.00 Set post 4 x 4 inches x 4 feet long
20 feet to the left,marked T,M, made
mound 4 feet Base 18 ins,high around post

Thence East 3,56 chs,A,6

..N,25°E,4,417,97..... A.7

.. N,17°E,4,48 chs, 12,45..... ..A,8

.. N.41°40'E, 15,57 28,02.....A,9

.. East 3,20 railroad N,S,31,22

8.30 Rock Bluff 4 feet high 39,52

8,25 Birch Creek 40 feet wide 47,77

,65 Right Bank48,42

3,60,.....,52,02 A,10

Thence S,59°30'E,3,03,.....,55,04 A,11

.. S,82°30'E 4.75.....59,79 A,12

.. N,61°50'E,4,45.....64,24 A,13

.. East 12,84... ..,77,08 R,T, Set post 4 x 4

inches x 4 feet long 30 feet East of Terminus,Marked R,T,No,745

Made mound 4 feet Base and 18 inches high around post,

I hereby certify that the foregoing Field Notes of Road No,745
are correct as Surveyed by me on the 29th and 30th,Days of April 1913

John W. Campbell.....
Deputy County Surveyor.