

FND 2 1/2" BC
PLS 933

TI PARTITION PLAT NO 1996-42

IN THE N 1/2 OF THE NW 1/4, S8, T3N, R29E

W.M.

DIKE R/W
DESCRIBED IN B 180 P.512

Surveyor's Certificate

I, Wayne O. Harris, Oregon Registered Professional Land Surveyor Number 346 being first duly sworn do depose and say that I have shown the surveyed parcels on this partition plat described as follows:

Parcel 1: North Half of Northwest Quarter of Section 8, Township 3 North, Range 29 East of the Willamette Meridian, Umatilla County, Oregon.

Exceptions

- As disclosed by the tax rolls the premises herein described have been zoned or classified for special use. At any time that said land is disqualified for such use said property will be subject to additional taxes and interest. Persons or parties acquiring title to said lands should check with the appropriate Planning department and Assessors office to verify zoning or classification.
- Easement for dike purposes disclosed in Deed to Frank J. Correa et ux, recorded March 28, 1945, Book 184, Page 437, Deed Records, and granted by Dillon Irrigation Company to the State of Oregon, recorded June 12, 1947, Book 180, Page 512, Deed Records.

APPROVALS:

Approved this 20 day of Sept 1996.
David H. Jones
Umatilla County Surveyor

Approved this 19 day of Nov 1996.
Wayne O. Harris
Umatilla County Planning Commission

Taxes are paid in full. Approved this 18th day of November 1996.
Anna Schuch
Umatilla County Tax Collector

SCALE 1" = 200'

LEGEND

- 5/8" REBAR PLS 346; 1" YELLOW CAP

DECLARATION

Know all men by these presents that we Richard J. Correa and Cathy J. Correa are the owners of the lands described in the Surveyor's Certificate and that we have caused the same to be partitioned in to the parcels in accordance with the provisions of ORS chapter 92, as shown on the attached map.

Richard J. Correa
Richard J. Correa

Cathy J. Correa
Cathy J. Correa



STATE OF OREGON
COUNTY OF UMATILLA SS

Subscribed and sworn before me on this 23rd day of SEP 1996.
Notary Public for Oregon. My commission expires 1 Aug 1999



NARRATIVE:

I located the North 1/4 corner, the Northwest corner and the Southwest corner of Section 8. I ran the North line and the West line of Section 8 and prorated the West line to determine the location of the South line of the North 1/2 of the Northwest 1/4 of said section. This distance checked within 0.31 feet of a line that had been accepted as said South line and monumented by an old fence line. The bearing of this fence agreed with the bearing of the North line of the section within 5". I accepted this fence line as being the true line and set out the boundaries of Parcel 2.



STATE OF OREGON }
COUNTY OF UMATILLA }
I certify that this instrument was received and recorded

ON November 19, 1996
at 12:00 o'clock P.M., in the record of
PLATS of said County.
YEAR NUMBER Slide
1996 42

OFFICE OF COUNTY RECORDS

By: GEORGIA MCNAUGHT
Records Officer

Fees \$ 25.00 No. 1996-225340

I CERTIFY THIS TO BE AN EXACT COPY.

Wayne O. Harris
PLS 346

POWER POLE AT 3 WAY FENCE INTERSECTION