

At 5415' 3/4" cross center line of Willow Street
 At 5675' 3/4" cross center line of Garden Street
 At 5945' 3/4" set monument 48" x 12" x 14" marked No. 5 at the intersection of center lines of High and Main Streets.
 At 6215' 3/4" cross center line of Cottonwood Street
 At 6475' 3/4" cross center line of Johnson Street
 At 6735' 3/4" cross center line of Thompson Street
 At 6995' 3/4" cross center line of College Street
 At 7255' 3/4" cross center line of Vincent Street
 At 7515' 3/4" set monument 32" x 13" x 14" marked No. 6 at the intersection of center lines of High and Mill Streets.

At 7775' 3/4" cross center line of Clay Street
 At 8035' 3/4" cross center line of Market Street
 At 8295' 3/4" cross center line of Post Street
 At 8555' 3/4" cross center line of Franklin Street
 At 8815' 3/4" cross center line of Union Street
 At 9075' 3/4" cross center line of State Street
 At 9335' 3/4" cross center line of Howard Street
 At 9595' 3/4" cross center line of Mason Street
 At 9855' 3/4" cross center line of Poyer Street
 At 10115' 3/4" cross center line of Hill Street
 At 10375' 3/4" set monument 36" x 12" x 14" marked No. 7 at intersection of High and Boise Streets.

In order to locate other Streets I run thence S. 23° 36' E. along the center line of Boise Street to the South boundary line of the Reserve Addition thence N. 66° 24' E.

At 260 ft. cross center line of Dean Street
 At 520 ft. cross center line of Stone Street
 At 780 ft. cross center line of Snow Street
 At 1040 ft. cross center line of Spring Street
 At 1255' 9/8" intersect monument No. 13 at the South East corner of Reserve Addition.

To locate the monuments and cross streets on the Court base line, begin at the monument at the intersection of the center lines of Court and Grange Streets, thence N. 89° 13' E.

At 260 ft. cross center line of Lee Street
 At 520 ft. cross center line of Stonewall Jackson Street.

At 780 ft. cross center line of Long Street
 At 1040 ft. cross center line of Beaubien Street
 At 1300 ft. cross center line of Jeff. Davis Street
 At 1464' 7/8" intersect monument No. 3, at the intersection of Court and Webb Street base line.

At 1560 ft. cross center line of River Street
 At 1820 ft. cross center line of Mission Street
 At 2080 ft. cross center line of Benedict Street

At 2340 ft. cross center line of Turk Street
 At 2600 ft. set monument No. 8 at intersection of center lines of Court and Hope Streets.
 At 2860 ft. cross center line of Transit Street
 At 3120 ft. cross center line of Eddy Street
 At 3380 ft. cross center line of Wyble Street
 At 3640 ft. cross center line of Summer Street
 At 3900 ft. cross center line of East Street
 At 4160 ft. cross center line of Point Street
 Thence S. 0° 47' E. 410 ft. cross center line of Turner Street, at 790 ft. intersect North side of La Grand Street, thence N. 89° 13' E. along the side of La Grand Street, 260 ft. cross center line of Wood Street, 376' 0/8" intersect East boundary line of the Reserve Addition.

In order to locate parallel streets North of Court Street, I begin at monument No. 8 on Court Street thence N. 0° 47' W. 405 ft. cross center line of Lewis St. 805 ft. cross center line of Church Street at 1180 ft. intersect South side of Park Street.

In order to locate the Reserve line East of Mill Street, I begin at the intersection of the Webb Street base line and the East side of Mill Street, thence N. 23° 36' W. 599' 6" to the Reserve line, thence N. 65° 10' E. to the East side of Grange Street, thence S. 0° 47' E. 53' 3/4" to the center line of Court Street.

In order to locate the corners of blocks on the Reserve line Eastward from Grange Street, I ascertain the departure for each 200 ft. and 60 ft., the course of the Reserve line being N. 65° 10' E. and that of the Court Street base line N. 89° 13' E. the angle included between these lines is 24° 03' for this angle the departure will be 89.255 ft. for each 200 ft. and 26.776 ft. for each 60 ft., with these departures the corners of all blocks on the Reserve line were ascertained and located.

Location of Corner to Sections 1, 2, 11 and 12 T. 2, N. R. 32 E., Willamette Meridian. Begin at S. W. corner of block 155 thence N. 17° 13' E. 46' 7" to the corner above described, where a rock 16" x 10" x 6" was set marked C1 and C11 on the opposite sides with a cross mark cut on the top.

Location of a 1/4 Section Corner. Beginning at the N. E. corner of block 183 thence S. 3° 41' E. 202' to the 1/4 section corner between sections 10 and 11 Township and Range being the same as above described, where a rock as originally set still