


STATE OF OREGON,
 COUNTY OF UMATILLA }
 I certify that this instrument was received and recorded
 ON June 16, 1998
 at 8:40 o'clock Am., in the record of
 PLATS of said County
 BOOK PAGE Slide
 13 123
OFFICE OF COUNTY RECORDS
 By: GEORGIA MCNAUGHT
 Records Officer
 Fees \$ 25.00 No. 1998-3310264



- ✕ Found Section Corner as Noted
- ⊗ Found Quarter Section Corner as Noted
- Set 5/8"x24" Iron Rebar w/ Plastic Cap "OR 2166LS"
- Found Monument as Noted
- [Record per Reference Doc #]

Basis of Bearings
 Bearings are Grid, Oregon Coordinate System of 1983, North zone, and based on observations from Athena NGS, theta c + 1° 28' 23".

Owner's Certificate

I, Clinton L. Sloan, and I, Connie L. Sloan, and I, Sheldon W. King, and I, Tracie L. King, joint owners of the lands described herein, do hereby acknowledge that we have caused this plat to be prepared and this land to be platted in accordance with ORS Chapter 92, and the City of Athena Subdivision Ordinance, and do hereby dedicate to the public the streets and alleys and easement shown hereon.

Clinton L. Sloan Connie L. Sloan
 Clinton L. Sloan Connie L. Sloan

Ken Bjorklund
 Notary
 Subscribed and sworn before me this 30 day of April, 1998.
 Notary Public for the State of OREGON
 Residing at Athens, OR
 My Commission Expires: Feb. 6, 2001

State of Oregon SS
 County of Umatilla



Sheldon W. King Tracie L. King
 Sheldon W. King Tracie L. King

Ken Bjorklund
 Notary
 Subscribed and sworn before me this 30 day of April, 1998.
 Notary Public for the State of OREGON
 Residing at Athens, OR
 My Commission Expires: Feb. 6, 2001

State of Oregon SS
 County of Umatilla



REGISTERED PROFESSIONAL LAND SURVEYOR
Dwight M. Bartleson
 OREGON
 JULY 26, 1985
 DWIGHT M. BARTLESON
 0216613
 Renew: Dec. 31, 1999

STATE OF OREGON, }
 COUNTY OF UMATILLA }
 I certify that this instrument was received and recorded
 ON June 16, 1998
 at 8:40 o'clock Am., in the record of
 PLATS of said County.
 BOOK PAGE Slide
 13 123 123
 OFFICE OF COUNTY RECORDS
 By: GEORGIA MCNAUGHT
 Records Officer
 Fees \$ 25.00 No. 1998-3310264

Approvals

Umatilla County Tax Collector
 Taxes have been paid in full.
Annita Schults
 Umatilla County Tax Collector

Umatilla County Assessor
John C. ...
 Umatilla County Assessor

Umatilla County Commissioners
William S. Hamrell
Emile M. Holloman
 Umatilla County Commissioners

City of Athena
 This partition plat and replat is hereby approved
 this 11 day of June, 1998.
 Plat Approval # 46-97
Kathleen ...
 Recorder - City of Athena

Umatilla County Surveyor
 This partition plat and replat is hereby approved
 this 10 day of June, 1998.
David H. ...
 Umatilla County Surveyor

Narrative of Survey

A survey to plat and replat the lots as shown.
 Survey commenced February 16, 1998. Instrument used was a Topcon GTS2-06. Four angles were measured by repetition for the control traverse.
 I found monuments as shown for the centerline of Hunt Street per the survey 97-184-B, records of the Umatilla County Surveyor. Bearings and distances from Knowlton's Addition were held from the Hunt Street monuments.
 I found as per the Plat of Schroeder Heights that the record distances as shown on Knowlton's Addition to the North Line of Section 19 are some 30 feet short. To assure that I had the East Line of Knowlton's Addition platted correctly, I used the record distances for Blocks 6 and 8. The computed distances match within a few hundredths of a foot for most of the blocks.

Reference Documents

- R01 Deed Book "D" at pages 131 & 227 & Plat Book 2 at page 4, Records of Umatilla County - Original Town of Centerville.
- R02 Plat Book 1 at page 117 - C.A. Roses Addition to the Town of Centerville.
- R03 Plat Book 1 at page 118 - Knowlton's Addition to the Town of Centerville.
- R04 Plat Book 12 at page 2 - Plat of Schroeder Heights
- R05 Map N-70-B, Records of the Umatilla County Surveyor
- R06 Map 87-21-A, Records of the Umatilla County Surveyor
- R07 Map 83-76-C, Records of the Umatilla County Surveyor
- R08 Map 95-159-B, Records of the Umatilla County Surveyor
- R09 Map 95-188-B, Records of the Umatilla County Surveyor
- R10 Map 95-200-B, Records of the Umatilla County Surveyor
- R11 Map 96-104-B, Records of the Umatilla County Surveyor
- R12 Map P-125-A, Records of the Umatilla County Surveyor
- R13 Map 97-184-B, Records of the Umatilla County Surveyor

NW Qtr NW Qtr Section 19, T4N, R35E, WM, Umatilla County, Oregon

A Plat of Sloan's Addition for Clint Sloan 247 W. College Athens, Oregon 97813		
Dwight M. Bartleson L.S. 7990 LaMar Gulch Road Athens, Oregon 97813 (541) 566 - 2397		
Drawn By: DMB	Date: Mar 1, 1998	Sheet 1 of 2

I hereby certify this to be a true and exact copy. Dwight M. Bartleson