



THE CENTERLINE OF HWY 11 WAS LOCATED FROM FOUND P.L. MARKS. THE E. LINE OF PROPERTY SURVEYED WAS ESTABLISHED PARALLEL TO THE N. R/W LINE OF THE HWY. AND 275.00 FT. WESTERLY THEREFROM, MEASURED ALONG THE N. LINE OF S.W. 1/4 SEC. 36, AS PER DEED TO EDWARDS, BR. 240, PG. 551. THE S. LINE OF PROPERTY SURVEYED WAS ESTABLISHED AS THE N. LINE OF CARR TRACT AS PER DEED, BR. 211, PG. 402. BOTH THE EDWARDS AND CARR TRACTS ARE CALLED TO IN THE DEED FOR PROPERTY SURVEYED, R. 38, PG. 1266.

LEGEND

- MONUMENT FOUND AS NOTED
- SET 1/2" x 30" STEEL ROD WITH BRASS TAG STAMPED "LS 934", OR AS NOTED.
- CALCULATED POINT, NOT FOUND OR SET.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1970
VICTOR M. MCLIND
934

SURVEY TO SET PROPERTY CORNERS
IN S.W. 1/4 SEC 36, T6N, R35E, W.M.
SURVEYED FOR WALTER ROLOFF
SURVEYED BY VICTOR M. MCLIND
JAN. 1985

RECEIVED BY
Umatilla County Surveyor

Date 1985
Rec'd By *bc*
No. 85-18-A

RLS 506
T6N R35E
535 | 536
52 | 51
T5N R35E
1964

SECTION CORNER
Found 2" IRON PIPE
WITH 2" BR. CAP
STAMPED AS SHOWN

COUNTY SURVEYOR
T6N
R35E
51
T5N
RLS 933 1980

Found 2 1/2"
BR. DISC
STAMPED AS SHOWN

BEARINGS ARE BASED ON ORE. STATE HWY DEPT. GRID
BEARING, CORRECTED TO TRUE.

85-18-A