

75N R36E
S17 S16
S20 S21
1985
R.L.S. 934

1985
S16
S21
R.L.S. 934

SEC. CORNER
FND. ROTTED LOCUST
POST IN MOUND OF
STONE, 4' W. OF W. END
OF OLD FENCE. SET 2" AL.
PIPE WITH 3/4" AL. CAP MTD.

1/4 CORNER
FND. MOUND OF STONE
AT VERY OLD FENCE
CORNER. SET 3/4" STEEL ROD
WITH 1 1/2" AL. CAP MTD AS SHOWN

1/4 CORNER
FND. STONE 6"
x 7", T ABOVE
GROUND, NEAR
FENCE CORNER,
FIRMLY SET,
USED BY STORMS
IN 1948.

1/4 CORNER
FND. 3/4" STEEL REBAR
WITH 1 1/2" AL. CAP
MTD. AS SHOWN

1/4
S21 S22
1978

SEC. CORNER
FND. STONE 18x11/2";
WITH INDISTINCT MORTARS,
IN MOUND OF STONE UNDER
N-S FENCE LINE, 45 LINKS
N. OF RAVINE, COURSE ABOUT
N. 85° W AS PER 1887
RE-SURVEY BY ARNOLD.
IN PLACE OF STONE I SET A
2"x30" AL. PIPE WITH 2 1/2" AL.
CAP MTD. AS SHOWN

75N R36E
S21 S22
S28 S27
1985
R.L.S. 934

S.W. CORNER
SE. 1/4 NW 1/4 Sec. 21

RECEIVED BY
Umatilla County Surveyor
Date 3-85
Rec'd By KA
No. 85-62-A

CURVE DATA

CURVE 1:
A = 1°05'25"
R = 2530.00 (Q.R. = 2500')
L = 48.14
C = 589°11'18"W, 48.14

CURVE 2:
A = 9°06'21"
R = 970.00 (Q.R. = 1000')
L = 154.16
C = 588°11'46"W, 154.00

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1979
VICTOR M. MCLIND
934

LEGEND

- MONUMENT FOUND AND USED FOR CONTROL, AS NOTED.
- SET CORNER AS NOTED FROM FOUND EVIDENCE.
- SET 1/2" x 30" STEEL ROD WITH 1" PLASTIC CAP MARKED "LS 934"
- CALCULATED POINT, NOT FOUND OR SET.

SURVEY IN SEC. 21, T5N, R.36E, W.M.
SURVEYED FOR VIRGINIA KELLY
SURVEYED BY VICTOR M. MCLIND, L.S. # 934
MARCH, 1985 SCALE: 1" = 100'
BEARINGS BASED ON SOLAR OBSERVATION ON 3-5-85

85-62-A

BREAKDOWN OF SECTION 21
SCALE: 1" = 1000'

NARRATIVE:
THE PURPOSE OF THIS SURVEY WAS TO DIVIDE OUT A 2 AC. PARCEL WHICH WAS RETAINED BY MY CLIENT WHEN FARM WAS SOLD. THE W. LINE OF THE 2 AC. PARCEL IS THE W. LINE OF SE 1/4 NW 1/4 S. 21. AS I FOUND NO RECORD OF A PREVIOUS SECTIONAL BREAKDOWN, I PROCEEDED TO SUBDIVIDE THE SECTION. I FOUND EVIDENCE AS SHOWN FOR THE N.E. 1/4 W. 1/4 CORNERS AND THE NW, SW, 1/4 SE. SECTION CORNERS. ALTHOUGH EVIDENCE WAS NOT CONCLUSIVE OF ORIGINAL LOCATION IN ALL CASES, I BELIEVE IT WAS THE BEST AVAILABLE EVIDENCE. I SEARCHED FOR THE S. 1/4 COR. BUT FOUND NO GOOD EVIDENCE, SO I PROPORTIONED ITS LOCATION. IT FALLS ON A FARMED FIELD SO I DID NOT MONUMENT IT. I RAN CLOSED TRAVERSES WITH THEODOLITE & EDM. TO TIE ALL CORNERS.

