



**SURVEYOR'S NARRATIVE:**

THE PURPOSE OF THIS SURVEY IS TO SET THE MISSING CORNERS OF LOTS 18 AND 19, BLOCK 4, OF NORTH HILL TERRACE FOR THE CONSTRUCTION OF A HOME ON LOT 18 AND POSSIBLE FUTURE CONSTRUCTION ON LOT 19. I FOUND ALL BUT 2 OF THE ORIGINAL CORNERS OF THESE LOTS WHICH WERE SET BY DON STAEBLER IN 1979. I RETRACED HIS ORIGINAL SURVEY TO SET THE TWO MISSING CORNERS.

SCALE  
1"=60'

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RECEIVED BY  
Umatilla County Surveyor  
Date 9-95  
Rec'd By KK  
No. 95-142-A

- SET A 5/8" X 30" REBAR WITH A PLASTIC CAP STAMPED 951.
  - FOUND A 5/8" REBAR -STAEBLER 1979-
  - FOUND A 1/2" REBAR -STAEBLER 1979-
- 6' UTILITY EASEMENT ON ALL LOT LINES

	ARC LENGTH	CHORD LENGTH	CHORD BEARING	RADIUS	DELTA	TANGENT
A	33.97	33.94	N 15°54'49"W	272.24	7°08'55"	17.01
B	15.71	14.14	S 64°29'17"E	10.00	90°00'00"	10.00
C	107.30	106.82	N 79°54'19"E	327.24	18°47'13"	54.14

SURVEY FOR: **DALE MORRELL**  
 LOTS 18 AND 19, BLOCK 4, NORTH HILL TERRACE  
 LOCATED IN THE SE 1/4 OF SECTION 33,  
 T 5 N. R 28 E. W.M. UMATILLA COUNTY, OREGON

EDWARDS SURVEYING  
 P.O. BOX 763  
 HERMISTON, OREGON 97838

7/18/95  
 JOB NO. S9506086  
 503-567-3336

95-142-A