



NARRATIVE

THE BEARINGS AND SURVEY ARE BASED ON THE BREAKDOWN OF THE SECTION BY MYSELF IN THE 1975 SURVEY FOR BOOTH AND BURNEY. IN THAT SURVEY I USED A BRASS SCREW AND WASHER AS THE SOUTH WEST CORNER OF THE SECTION AS OTHER SURVEYORS BEFORE ME HAD, THOMPSON AND SHEA HAVE RECORDED SURVEYS USING THAT MONUMENT AS THE CORNER, THAT BRASS SCREW AND WASHER IS NEAR THE CENTER OF PUNKIN CENTER ROAD. IN SUBSIQUENT SURVEYS I FOUND THAT THE NORTH WEST CORNER OF SECTION 5, T4N, R29E, (A STUMP WHICH USED TO HAVE AN IRON ROD IN IT) HAS A LATITUDE OF APPROXIMATELY 8 FEET NORTH OF THAT OF THE ABOVE MENTIONED SCREW AND WASHER AND LIES NORTH OF THE PAVEMENT.

IN SURVEYS DONE IN SECTIONS 5 AND 6, T4N, R29E. I AND OTHER SURVEYORS USED THAT MONUMENT. THIS HAS RESULTED IN AN OVERLAP ON THE PUNKIN CENTER RIGHT OF WAY. IN THIS SURVEY I RESEARCHED THE COUNTY RECORDS AND FOUND ONE DONE IN 1913 BY J. KIMBRELL RECORDED IN BOOK 2, PAGE 243, IN THE SOUTHEAST 1/4 OF SECTION 32. THE TWO MONUMENTS I FOUND WHICH I BELIEVE TO BE HIS, FIT MY SURVEY OF 1975.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 15, 1975
G. DENNIS EDWARDS
951

SURVEY FOR: DICK FUNKE

LOCATION N.W. 1/4 SE. 1/4

SEC. 32, T5 N, R29 E, W.M., UMATILLA COUNTY, OREGON

DATE 8-3-79

SCALE: 1" = 200'

● MONUMENTS FOUND (00) OF RECORD

○ 1/2" IRON RODS SET JOB NO. S 7907185

EDWARDS SURVEYING
567-8336

P. O. Box 763
Hermiston, Ore.

Q-1143-A