





FIELD NOTES

Surveyed by:  
Verl K. Fraley #183

For Surveys in Stanfield, Umatilla Co., Ore  
Section 32, T. 4 N., R. 29 E., W.M.

On Coe Ave

Found  $\frac{3}{4}$ " I.P. at the centerline of Coe Ave. and the East line of Dunne St. This point is the N.W. Cor of the S.W.  $\frac{1}{4}$  of the S.E.  $\frac{1}{4}$  of Sec. 32.

Found  $\frac{3}{4}$ " I.P. at the centerline of Coe Ave. and the West line of Wayne St.

Produced line easterly on centerline of Coe Ave 562.8 feet from the  $\frac{3}{4}$ " I.P. on West line of Wayne St. Set  $\frac{5}{8}$ " I.Pin at centerline of Sloan St. & Coe Ave for the S.W. Cor of N.E.  $\frac{1}{4}$  of S.E.  $\frac{1}{4}$  Sec. 32. From this point layed out tracts as shown on accompanying sketch. Continuing Easterly

1313.5

Set Nail in pavement for N.E. Cor of S.E.  $\frac{1}{4}$  of S.E.  $\frac{1}{4}$   
From this corner on true bearing N.0°-15'E.

1314.3

Found  $12 \times 12 \times 18$ " boulder 1 ft. under road surface. Found no markings on it. Set temp. point for E.  $\frac{1}{4}$  cor.

On Centerline Sloan St. On true bearing N.0°-06'E.

659.62

Set stake for N.W. cor of S.W.  $\frac{1}{4}$  of N.E.  $\frac{1}{4}$  of S.E.  $\frac{1}{4}$  Sec. 32.

1319.22

Set  $\frac{1}{8}$ " I.Pin for N.W. cor of N.E.  $\frac{1}{4}$  of S.E.  $\frac{1}{4}$ .

On Centerline County Road (East & West Quarter line Sec. 32)

Established centerline of County Road from this point and the temporary E.  $\frac{1}{4}$  Cor Sec. 32.

From the  $\frac{1}{8}$ " I.Pin N.W. cor of N.E.  $\frac{1}{4}$  of S.E.  $\frac{1}{4}$  on true bearing of S 89°-48'E

1314.95

Set 1" I.Pin 8" under road surface just east and alongside  $12 \times 12 \times 18$ " boulder for the E.  $\frac{1}{4}$  corner of Sec. 32.

References: Nail in P.Pole bears N.60°W  
dist. 32.1 ft.  
Nail in P.Pole bears S.45°E  
dist. 34.4 ft.

From E.  $\frac{1}{4}$  cor. Sec. 32 on true bearing N.89°-48' W

657.48

Set  $\frac{1}{8}$ " I.Pin.

986.22

" " " " From these two points layed off tracts as shown in accompanying sketch.

1314.95

$\frac{1}{8}$ " I.Pin

2630.7

Dug  $\text{cor}$  but found no trace of an original corner.

2680.13

Set  $\frac{3}{4}$ " I.Pin for centerline Dunne St. This point also set from an angle of 90° off centerline Coe Ave. and Dunne St. Measured 1324 ft. from Coe Ave.

3333.7

Set  $\frac{3}{4}$ " I.P. on West right of way line of Highway No. 11.

3951.55

Set  $\frac{3}{4}$ " I.P. for S.W. cor of S.E.  $\frac{1}{4}$  of N.W.  $\frac{1}{4}$  Sec. 32

From last two points layed off Tract as shown in accompanying sketch.



For surveys in Stanfield, Umatilla co., Ore

From E.  $\frac{1}{4}$  corner Sec. 32 (Continued)

5272.4

Set 1" I.Pin for temp. W.  $\frac{1}{4}$  corner Sec. 32. This point agrees with an angle of  $41^{\circ}-33'$  turned off the centerline of the Railroad at a point 889.4 Northwesterly along the centerline of the main track from its point of intersection with the centerline of Coe Ave.