

Field Notes
Collins Survey

Surveyed June 1950
By V. R. Fraley
Reg. # 183

I began the survey at the East $\frac{1}{4}$ corner of Section 1, T. 4 N. R. 28 E., W. M. From the east line of the Section I turned an angle of $89^{\circ}-44'$ to the left and ran a distance of 665.72 feet where I found a 1" Iron Pipe, which had apparently been set by others. As this point checked with my calculations, I then ran on a bearing of $S.0^{\circ}-27' W.$ 1328.86 feet and set a $1/2"$ Iron rod for the S. W. Corner of the S. E. $\frac{1}{4}$ of the N.E. $\frac{1}{4}$ of the S. E. $\frac{1}{4}$ of the said Section 1. Then in order to thoroughly check my work I continued ^{to} on the South line of the Section and measured 664.87 feet $S. 89^{\circ}-20'$ to the S. E. Corner of the Section, which is a 6" by 6" by 12" stone.

I layed off the 1 acre tract as shown on the accompanying sketch.

Q-1348-Ax