



found evidence of fence corner

NARRATIVE:

Purpose of this survey was to establish the South sixteenth corner center to center and the Southeast sixteenth corner of Section 35, T.6N., R.31E., W.M. The Brass caps set by the BLM. were set in 1980 during a survey involving T.5 & 6N., R.31E., W.M. The bearings and distances are as shown on an unofficial sketch provided the County Surveyor's office upon completion of the BLM. survey work. The northeast corner of the Section was a fence post that agreed closely with original G.L.O. bearings and distances. This point was accepted and monumented. The 5/8" x 30" iron pin set is approximately 5' west of the Juniper Canyon roadway.

LEGEND:

- denotes 2 1/2" Brass Cap set on a 2 1/2" x 30" iron pipe set by BLM in 1980.
- denotes 2" Brass Cap stamped "Umatilla County Surveyor" on a 1 1/2" x 30" iron pipe set
- denotes 5/8" x 30" iron rod w/aluminum cap stamped PLS 933 set
- x- denotes fence find

RECEIVED BY
 Umatilla County Surveyor
 Date 2-15-83
 Rec'd By B.C.C.
 No. 83-08-B

David H. Klee

K KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon	SCALE 1" = 500'
	DATE 1-26-83
Survey for THORNE & MAUTZ	DRN. BY M.L.D.
Sec. 35, T.6N., R.31E., W.M.	CKD BY D.H.K.
	DRNG. NO. 83-08C