



NARRATIVE:

The purpose of this survey was to establish the property corners of that parcel belonging to First American Banking Company, which parcel is the East half of Block 18 of the Original Town of Pendleton.

Control was based on the centerline monuments at Main and Court and Main and Dorion. We projected down from these to establish the intersection of Byers and S.E. First.

Two Brass Screws and Washers established by the Corps of Engineers were tied and used to establish the Levee right of way alignment.

Bearings are based upon City of Pendleton local grid taken from the Main Street monuments.

- denotes set 5/8" x 30" iron pin with aluminum cap stamped PL5 933
- denotes found 1/2" Brass Screw & Washer on 1/2" iron pipe
- denotes found monument

Detail of wall along West line of East half of Block 18
n.t.s.

K KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1" = 50'	Drn. By DHK	Drng. No. 84 IC	Revision 1
	Date 1-6-84	Ckd. By DHK	Job No. 83155	Revision 2
SURVEY FOR FIRST AMERICAN EAST HALF BLOCK 18 ORIGINAL TOWN OF PENDLETON	REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H Klein</i>	RECEIVED BY Umatilla County Surv. yor Date <u>4/5/84</u> Rec'd By <u>bc</u> No. <u>84-35-B</u>		