



NARRATIVE:

The purpose of this survey was to establish the Section corner common to Sections 17, 16, 20 and 21, and also to establish the North line of Section 20 for the purpose of erecting power lines along the North lines of said Sections 20 and 21.

Bearings are based on a survey by Krumbein Engineering for Eagle Ranches dated 7-24-81, Umatilla County Surveyor Drawg. No. 5-113-B. The monuments found, with the exception of the NW corner of Section 19, are of the same drawing number.

The corner common to 17, 18, 19 and 20 was not set due to lack of reliable evidence. The North line of Section 20 was established by measuring between existing fence lines and roads lying West of Highway 206.

- denotes set 2 1/2" Brass Cap on a 2 1/2" x 30" iron pipe
- denotes find 2 1/2" Brass Cap
- denotes find 2 1/4" i. pipe w/stone along side

K	KRUMBEIN ENGINEERING LTD.		Scale 1"=1000'	Drn. By MLD	Drng. No. 84-18C	Revision 1
	ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon		Date 5-5-84	Ckd. By DHL	Job No. 84-40	Revision 2
Survey for EAGLE RANCHES			David H. Krumbein		RECEIVED BY Umatilla County Surveyor Date 5/30/84 Rec'd By <i>bc</i> No. 84-56-B	
Secs. 16, 17, 18, 19, 20 & 21, T3N, R28E, W.1M.						