



Top of levee of the Walla Walla River formerly the Bank of Tum-a-lum River

**NARRATIVE:**

The purpose of this survey was to establish the boundaries of that property as described in Book 342, Page 164 and to divide out a 6000 square foot parcel therefrom for Jones.  
 Bearings are based on the North line of the Southwest one-quarter of Section 1, being North 89° 49' 30" West as shown on the South line of the Holben Addition Plat and shown on the Umatilla County Surveyor Drwg. Nos. M-17-B and P-971-C. The North line of the Southwest one-quarter is also the North line of the original Plat of Freewater. The West and South lines of this parcel are defined by descriptions calls from the Plat of Freewater and our ties to the monuments shown. The East line is defined by the Top of the Levee along the Walla Walla River.

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes found 3/8" iron pin referenced as spike on Co. Surveyor Drwg. Nos. P-971-C and M-17-B
- denotes found 1/2" iron pin referenced on County Surveyor Drwg. No. P-144-A.
- denotes found 1/2" iron pin in a monument box referenced on Co. Surveyor Drwg. Nos. P-971-C and M-17-B.
- denotes found 3/8" iron pin referenced on County Surveyor Drwg. Nos. P-144-A and 84-22-A.

<b>KRUMBEIN ENGINEERING LTD.</b> ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=60'	Drn. By MLD	Drng. No. 84-23C	Revision 1
	Date 5-31-84	Ckd. By DHH	Job No. 84-60	Revision 2
Survey for  <b>JONES</b>		REGISTERED PROFESSIONAL LAND SURVEYOR <b>David H. Krumbein</b> OREGON JULY 17, 1970 DAVID H. KRUMBEIN 933		RECEIVED BY Umatilla County Surveyor Date 10/84 Rec'd By bc No. 84-112-B
NE 1/4, SW 1/4, Sec. 1, T5N, R35E, W1M.				