



SE⁴N.W.⁴ S. 2-T5N-R35E.W.M.

TAX LOT 200
WILTFONG

LEGAL DESCRIPTIONS

TRACT "A" :
Beginning at a point in the North line of the Southeast Quarter of the Northwest Quarter of Section 2, T 5 N, R 35 E.W.M., said point being 356.00 feet S 89°57'06" E, measured along said North line from the Northwest corner thereof; thence continue S 89°57'06" E, along said North line 82.00 feet; thence S 0°27'37" W, a distance of 130.00 feet; thence N 89°57'06" W, parallel to the aforesaid North line of the Southeast Quarter of the Northwest Quarter, a distance of 82.00 feet; thence N 0°27'37" E, a distance of 130.00 feet to the Point of Beginning. SUBJECT TO the public road along the North side of said premises. Containing 8200 Square feet.

TRACT "B" :
Beginning at a point in the North line of the Southeast Quarter of the Northwest Quarter of Section 2, T 5 N, R 35 E.W.M., said point being 438.00 feet S 89°57'06" E, measured along said North line from the Northwest corner thereof; thence continue S 89°57'06" E, along said North line 83.50 feet to the Northwest corner of that tract of land conveyed to American Can Company by deed recorded in Book 172, Page 628, Deed Records of Washtilla County, Oregon; thence S 0°27'37" W, along the West line of said American Can Company Tract a distance of 130.00 feet; thence N 89°57'06" W, parallel to the aforesaid North line of the Southeast Quarter of the Northwest Quarter, a distance of 83.50 feet; thence N 0°27'37" E, a distance of 130.00 feet to the point of beginning. SUBJECT TO the public road along the North side of said premises. Containing 8350 square feet.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Ronald L. Munns

OREGON
JUNE 15, 1975
RONALD L. MUNNS
1052

"R" = Record "M" = Measured
() Denotes data from Dwyer survey
○ = 1/8" Iron pin set, unless noted.

SURVEYOR'S CERTIFICATE

THIS MAP CORRECTLY REPRESENTS A SURVEY MADE BY ME OR UNDER MY DIRECTION IN CONFORMANCE WITH THE REQUIREMENTS OF THE SURVEY RECORDING ACT IN _____, 19____.

Certificate No. ~~1059~~

~~AUDITOR'S CERTIFICATE~~ N/A

FILED FOR RECORD THIS _____ DAY OF _____ 19____ AT _____ IN BOOK _____ AT PAGE _____ AT THE REQUEST OF _____

COUNTY AUDITOR _____

RECEIVED BY
Washtilla County Surveyor
Date 7-3-85
Received by RLM
No. 85-80-B

RONALD L. MUNNS	
LICENSED LAND SURVEYOR	
2nd and W. Main Walls, WA 98382 Phone 525-7180	
Surveys	A SURVEY
Descriptions	OF WILTFONG PROPERTY FOR
Sub Divisions	BUZZ WRINKLE
Date	5/31/84
Drawn By	RLM
Checked By	RLM
No.	5705