



**NARRATIVE:**

The purpose of this survey was to set the corners of the SW 1/4 of Section 4, T3N, R33E, W.M., for Ronnie Belzma. Three of the corners of Section 4 were established or found in a survey by this firm for Jack Stevens, Umatilla Co. Surveyor No. S-153-B. At the SE corner of Section 4 there was a post which a local farmer said that he thought the corner was 8 to 10 feet North of the post. The distance from the post to a railroad spike at the SE corner of Section 3 fit within 4 feet and from the same post South to the SW corner of Section 10 fit within about 4 feet. The distance from the post to the NE corner and to the SW corner of Section 4 did not fit well, 62 feet and 59 feet. In the survey for Stevens we used many of the intersections of fence, plowlines, and roads for the section lines, therefore in this case we put the SE corner of Section 4 10 feet North of the post.

- denotes set 2 1/2" Brass Cap
- denotes find post
- denotes find BC, Co. No. S-153-B
- denotes find R/A spike, Co. No. G-526-A
- denotes intersection of county roads, set 2 1/2" BC.
- ( ) denotes GLO distance

<b>KRUMBEIN ENGINEERING LTD.</b> ENGINEERS - SURVEYORS - PLANNERS 381 S.E. Second Pendleton, Oregon	Scale 1"=100'	Dwn. By MLD	Drng. No. 85-59C	Revision 1
	Date 10-3-85	Set. By DVK	Job No. 85-123	Revision 2
Survey for <b>RONNIE BELSMA</b> Secs. 4 & 5, T3N, R33E, W.M.		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbein</i> OREGON JULY 22, 1948 DAVID H. KRUMBEIN 933	RECEIVED BY Umatilla County Surveyor Date <u>1-10-86</u> Rec'd By <u>RA</u> No. <u>86-3-B</u>	