



NARRATIVE

The purpose of this survey was to establish the East line of that tract of land conveyed to Bill and Penny Andrews as recorded in Roll 112 on Page 967 of the Deed Records of Umatilla County.

The Deed begins at a point 396 feet East of the intersection of the original Northernly right-of-way line of O.R. & N. Co. Railroad and the West line of the Southeast quarter of the Northwest quarter, Section 10, T24N, R32E. I tied to the Center of said Northwest quarter and corners West of the Center as shown on County Surveyor No. G-321-C, then projected an angle South as shown on County Surveyor Nos. G-321-C and G-300-B of a bearing of 50°57'05\"/>

The North-South centerline of said Northwest quarter and Northernly right-of-way were intersected and the distances from Deed then used to establish the East line.

Bearings are based upon a survey for Mrs. Terry, County Surveyor No. I-200-A that shows the bearing from the Center of the Northwest quarter to the Southeast corner of said Mrs. Terry properly as 546°23'50\"/>

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 935
- denotes find 1 1/2" I.D. iron pipe
- denotes find 20 penny Nail, Co Surveyor No. G-321-C calls for an iron pipe
- ▽ denotes find 1" O.D. iron pipe, Co Surveyor No. G-321-C
- denotes find R/R Spike
- ▣ denotes find R/R Spike of Terry Survey, Co. Surveyor No. I-200-A
- denotes find 3/8" iron pin set for Jones, County Surveyor No. G-1897-B
- () denotes Deed Call
- [] denotes Record Call

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 351 S.E. Second Pendleton, Oregon	Scale 1"=100'	Map No. 1120	Job No. 88-33	Revision 1
	Date 8-31-88	Drawn By D.H.K.	Job Title 88-33	Revision 2
Survey for ANDREWS		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbain</i> GREGG COUNTY DAVID H. KRUMBEIN		DRAWN BY Umatilla County Surveyor Date 12-88 Rec'd By RA No. 88-77-B

SW 1/4, Section 10, T24N, R32E, W.1M.