



NARRATIVE:

The purpose of this survey was to establish the boundaries of three parcels in the East half of the NE 1/4 of the NE 1/4 of Section 36, T4N, R36E, W1M. This section was previously broken down by this firm in a survey for Giger and Beard, Co. No. 85-164A. This survey was used except for the East quarter corner which set 1.07 feet to far North of its location as shown on Streamer's survey, Co. No. L-58B. An Affidavit of Correction is being filed for this error. I used the corrected location to set the corners for these parcels.

Deeds used were Olmstead to Grote, Roll 16A, Page 1067; Zellers to Olmstead, Roll 149, Page 1086; and Miller to Zellers, Roll 140, Page 520. Everything fit well except the North line which has an intrusion by the State Highway as shown. The County has a thirty foot right-of-way along the North line of the Section for County Road No. 678.

Bearings are from a survey for Napier, Co. No. 84-30B, for the North line of the Northeast quarter being $589^{\circ}55'39''E$.

- denotes set 3/8" x 30" iron pin with aluminum cap stamped PLS 933
- denotes find 2" iron pipe 6" below roadway with 4" pipe to surface
- ⊙ denotes find 2 1/2" Brass Cap on 2 1/2" iron pipe, Co. Surveyor No. 84-30B
- denotes find 3/4" iron rod, Co. Surveyor No. R-45C
- ⊠ denotes find Brass Cap, Co. Surveyor No. R-45C
- △ denotes find 5/8" iron pin with aluminum cap stamped PLS 933
- denotes find 2 1/2" Brass Cap, Co. Surveyor No. 85-164A

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 381 S.E. Second Pendleton, Oregon	Scale As shown	Drn. By MLD	Drng. No. 88-09C	Revision 1
	Date 7-13-88	Cl'd. By DHL	Job No. 88-24	Revision 2
Survey for HERNDON-ZELLER		REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbain</i>		RECEIVED BY Umalla Treedy Surveyor Date 12-88 Rec'd By KA No. 88-77-B
E 1/2, NE 1/4, NE 1/4, Sec 36, T4N, R36E		OREGON JULY 17, 1970 DAVID H. KRUMBEIN 639		