



NARRATIVE

The purpose of this survey was to establish the boundaries of a parcel for a Conditional Use Permit for a non-farm dwelling.

The North line was established along the Section line of Section 35 as defined by a Brass Cap at the Northeast corner as set by this firm in a survey for the City of Weston in 1983, County Survey No. 84-32B, and a stone found at the North quarter corner.

The East line was established from the centerline of Pine Creek Road. The West and South lines were established as requested by the Client to establish the size of the parcel required.

The bearings are based upon NGS Station "Athens" coordinates, 1927 datum as used in the survey for the City of Weston.

- denotes 1rd 2 1/2" Brass Cap on a 1 1/2" iron pipe County Survey No. 84-32B
- denotes 1rd stone from 1865 GLO survey notes
- set 3/8" x 30" iron pin with aluminum cap stamped PLS 933

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 381 S.E. Second Portland, Oregon	Scale: 1"=100' Date: 8-4-89	Prepd By: MLD Check By: DMK	File No: 83-16C Date: 83-26	Revision 1 Revision 2
	Survey for PIERSOL		RECEIVED BY Date: 3-90 Initials: [Signature] No.: 90-17-B	
NW¼, Sec 35, T4N, R35E, W1W				