



**NARRATIVE OF SURVEY**

THE PURPOSE OF THIS SURVEY WAS TO LOCATE AND MONUMENT THE BOUNDARIES OF A 1.54 ACRE NET AREA PARCEL FOR THE UMATILLA RESERVATION HOUSING AUTHORITY. THE ZONING AUTHORITY FOR APPROVAL OF ANY LAND DIVISION IS THE DEPARTMENT OF NATURAL RESOURCES OF THE CONFEDERATED TRIBES OF THE UMATILLA INDIAN RESERVATION.

THE SURVEY IS LOCATED IN ALLOTMENT UM 52, WHICH IS THE W 1/2 OF THE NW 1/4 OF SECTION 5, T1N, R38E, W4M. THE NW CORNER OF SECTION 5 WAS RE-ESTABLISHED AS SHOWN ON RECORDED SURVEY NO. 52-22-B. A WITNESS CORNER MONUMENT WAS FOUND FOR THE WEST 1/4 CORNER OF SECTION 5. THIS WITNESS CORNER MONUMENT (ORIGINALLY LOCATED 20 FEET EAST OF THE CORNER POINT) WAS SET BY C.E. REDFIELD IN 1919. THE MONUMENT HAS BEEN TORN OUT OF THE GROUND BY FARMING OPERATIONS BUT IS LOCATED AT THE WEST END OF A WELL DEFINED FENCE BERM AND FIELD LINE APPROACHING FROM THE EAST. AFTER SURVEYING 1 1/2 MILES TO THE SOUTH AND RECOVERING THE SOUTHWEST CORNER OF SECTION 5, I RE-ESTABLISHED THE WEST 1/4 CORNER OF SECTION 5 AT THE INTERSECTION OF THE OLD NORTH-SOUTH ROADBED OF PUBLIC ROAD NO. 5084 AND THE WELL DEFINED FENCE BERM APPROACHING FROM THE EAST.

BEARINGS ARE BASED ON THE LINE BETWEEN MONUMENTS AT THE NW CORNER AND NORTH 1/4 CORNER OF SECTION 5. THIS BEARING BASE IS THE SAME AS RECORDED MAP NO. 84-40-B.

RIGHT-OF-WAY WIDTH FOR THE COUNTY ROAD WAS FURNISHED BY THE UMATILLA COUNTY ROAD DEPARTMENT.

THIS SURVEY WAS MADE WITH A 2 PERSON CREW USING A LIETZ SET 3-B TOTAL STATION AND LIETZ SDR 22 ELECTRONIC FIELD BOOK.

**LEGEND**

- - MONUMENTS FOUND AS NOTED.
- - FD. 5/8" IRON PIN WITH 1 1/2" YELLOW PLASTIC CAP MARKED "W.R. WELLS, PLS 1106", PER MAP NO. 42-34-B.
- (XOX)RI - RECORD BY C.E. REDFIELD, U.S. INDIAN SERVICE SURVEYOR, FROM 1919 SURVEYS.
- - INDICATES LOCATION OF FOUND STAKE, PLACED BY OTHERS.
- ⊕ - LOCATION OF GEOTECHNICAL AUGER HOLE.

REGISTERED PROFESSIONAL LAND SURVEYOR  
*William R. Wells*  
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

WILLIAM R. WELLS, PLS  
357 N.E. HWY. 11  
P.O. BOX 1696  
PENDLETON, OR 97801  
PHONE: (503) 276-6362

DATE: 12-27-91 DR. BY: WEG  
CK. BY: WRW NO: 91-114

PROJECT:  
UMATILLA RESERVATION HOUSING AUTHORITY PROJECT: 12010

PARTICIPANT:  
DEE WILLIAMS

SITE NO.: 17  
DWELLING TYPE: 3 BEDROOM

D:\BILLO\WILLTPO